

Scotts Bluff National Monument
Oregon Trail Ruts Landscape Study
and Environmental Assessment ■ 100% Report

542 **Character Area B2**

543 Character Area B2 is located to the west of Character Area B1 and Mitchell Pass. This
544 Area contains documented emigrant trail resources that are visible. The trail rut resources in
545 this area are braided trails that are in most cases vegetated. The area is one of secondary
546 visitor use although with no formal walking trails in this area.

547 **Existing Condition**

- 548 ■ The trail topography within this area is gently sloped to the west with the exception
549 of a large knoll on the east end of the character area. Ravines flank both sides of the
550 trail resources.
- 551 ■ The views and vistas of Scotts Bluff, South Bluff and beyond are prevalent
552 throughout the Character Area.
- 553 ■ Multiple braided trail ruts exist throughout the character area due to the gentle
554 topography and ability of the wagons to spread out in this area.
- 555 ■ Vegetation encroachment has occurred throughout the trail causing less erosion.
- 556 ■ The only contemporary improvements have been the addition of compatible
557 wooden trail markers.

558 **Analysis**

559 **Trail Rut Resource**

- 560 ■ The trail ruts are Class 1 (unaltered original trail) throughout the character area. All
561 of the trail rut resources in this area are contributing resources.
- 562 ■ According to monument staff, Character Area B2 receives little visitor use. No
563 formal visitor trails exist.
- 564 ■ Erosion potential is low due to vegetated ruts and moderate topography. Vegetation
565 encroachment has helped reduce the erosion within and adjacent to the trail ruts by
566 stabilizing the soil.
- 567 ■ The multiple trails in this area provide an example of how emigrant wagons spread
568 out in flatter topography on the west side of Mitchell Pass.
- 569 ■ The trail ruts in this area are more difficult to visibly discern than in Character Areas
570 A and B1 due to vegetation encroachment, the braided nature of the trails and non-
571 use. While the growth of vegetation (grasses) helps stabilize soils and reduce
572 erosion, it also reduces the visibility of trail ruts, primarily in the flatter sections.

**Scotts Bluff National Monument
Oregon Trail Ruts Landscape Study
and Environmental Assessment ■ 100% Report**

573 *Visitor Experience*

- 574 ▪ Visitors who visit this area have an opportunity to experience the inspiring views of
575 Scotts Bluff and South Bluff in much the same way emigrants did.
- 576 ▪ The emigrant trail in this area is more difficult for visitors to locate and view than the
577 trail in Character Areas A and B1 and receives less use.
- 578




579 **Figure 3 - 35.** Trail ruts in wide flat area in Character Area B2 (2009)
580 (MBD DSC_0105.JPG)
581
582

Scotts Bluff National Monument
Oregon Trail Ruts Landscape Study
and Environmental Assessment ■ 100% Report



583
584
585
586

Figure 3 - 36. View of Scotts Bluff, South Bluff and Mitchell Pass from Character Area B2 (2009) (MBD DSC_0109.JPG)



587
588
589
590

Figure 3 - 37. Trail ruts at the knoll (west end) of Character Area B2 (2009) (MBD DSC_0114.JPG)


**Scotts Bluff National Monument
Oregon Trail Ruts Landscape Study
and Environmental Assessment ■ 100% Report**

591
592

Table 3: Character Area B2 - Small Scale Features

<i>Feature</i>	<i>Figure #</i>	<i>Description</i>	<i>Condition</i>	<i>Contributing/Non-contributing</i>
Boy Scout Trail Marker	3-24	Wood post with emblems indicating trail location of Oregon Trail/California Trail/Pony Express	Good	non-contributing compatible <i>outside period of significance</i>

593



Trail Classification

- Class 1 - Unaltered Original Trail**
— (solid red line)
- Class 2 - Used Original Trail**
- - - (dashed red line)
- Class 3 - Verified Original Trail**
· · · (dotted red line)
- Class 4 - Impacted Original Trail**
- - - - (long-dashed red line)
- Class 5 - Approximate Original Trail**
- - - - - (short-dashed red line)

Legend

- ① **Remnant Fenceline Topography - From Prior Agricultural Practices Post Oregon Trail**
- ② **Multiple Trail Ruts Through Flat Topography - Class 1 (Unaltered Original Trail)**
- ③ **Multiple Trail Ruts Through Ridge - Class 1 (Unaltered Original Trail)**
- ▲₃₋₁ **Photo Reference Figure #**




FIGURE 3 - 38 UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE SCOTTS BLUFF NATIONAL MONUMENT	<small>TITLE OF PROJECT</small> OREGON TRAIL RUTS LANDSCAPE STUDY <small>ENVIRONMENTAL ASSESSMENT</small> <small>DRAWING TITLE</small> CHARACTER AREA B2 - EXISTING CONDITIONS <small>NAME OF PARK</small> SCOTTS BLUFF NATIONAL MONUMENT <small>REGION</small> <small>COUNTY</small> <small>STATE</small> MIDWEST SCOTTS BLUFF NEBRASKA
--	---

