



LOWER PLAZA REHABILITATION

AREA A:

- REMOVE ALL PAVING. SALVAGE DECORATIVE PANELS. EXISTING CURBS & BORDERS TO REMAIN IN PLACE.
- REMOVE & REPLACE ALL DRAINAGE PIPING.
- INSTALL EXPOSED AGGREGATE PAVING TO MATCH ORIGINAL. INSTALL SALVAGED PANELS.
- REPLACE DRAIN GRATES W/ SLOTTED CAST IRON.

AREA B:

- REMOVE ALL PAVING INCLUDING CURBS. SALVAGE APPROX. 50% FOR REINSTALLATION. SALVAGE CHESSBOARD PIECES FOR REINSTALLATION.
- REMOVE & REPLACE ALL DRAINAGE PIPING.
- INSTALL SALVAGED PANELS & NEW PANELS W/ PEBBLE-DASH STRIPED TO MATCH EXISTING.
- REPLACE ALL DRAINAGE GRATES W/ SLOTTED CAST IRON.
- REMOVE & REPLACE ALL GRANITE COBBLES. ASSUME 50% SALVAGE FOR REINSTALLATION.

AREA C:

- REMOVE ALL PAVING INCLUDING CURBS. SALVAGE APPROX. 50% FOR REINSTALLATION.
- REMOVE & REPLACE ALL DRAINAGE PIPING.
- INSTALL SALVAGED & NEW PAVING TO MATCH EXISTING.
- REPLACE ALL DRAINAGE GRATES W/ SLOTTED CAST IRON.