## National Park Service U.S. Department of the Interior




## Olympic Hot Springs Road Olympic National Park



## **Project Location**

Olympic Hot Springs Road





#### Background-Elwha Valley Access

- Trailheads
- Visitor Contact Station
- Picnic Areas
- River Boating Access
- Glines Canyon Overlook
- Olympic Hot Springs
- Administrative access
- Annual Visitation -180,000




## Background: Dam Removal










## Post Dam Removal Flood Damage



## **Road Flood Damage**



#### **Activities to date**

- Concept comparisons
  - Reroute(s)
  - Bridge(s)
  - Viaduct(s)
  - Minor raise
  - Tunnel
  - No Action
  - Strategic retreat

- Geotechnical investigations
- Field visit with Tribe
- Civic engagement 12/2018
- Agency meetings
- Emergency repairs
  - Bridges
  - Bank stabilization
  - Road closure

#### Schematic Alternatives


No Action (\$650,000—Limited "retreat")

2004 Dam Removal SEIS states that road access shall be maintained
NEPA requires consideration of no action alternative

Realign road to edge of floodplain (\$8,300,000)
PREFERRED ALTERNATIVE

Raise road across floodplain (\$31,000,000)
Raises road approximately 15' above current elevation

#### **Schematic Alternatives**





#### Criteria Considered

Sustainable/reliable visitor access

Character of existing corridor access

Restoration of habitat for T&E fish species

- Riparian habitat disturbance
- Archeological disturbance
- Upland habitat disturbance
- Operational efficiency
- Capital costs
- Private property access
- Constructability



#### **Project Scope**

- 1. Realign One Mile Olympic Hot Springs Road (Elwha Road) out of Elwha River Floodplain
- New alignment east of existing road
- 20' wide road, paved
- Almost entirely out of flood plain
- Retaining walls where constrained
- Bank stabilization/log jams
- Utilities underground
- 2. Rehabilitate 7+ Miles of Olympic Hot Springs Road

#### Advantages Preferred Alternative

- Restore Access while minimizing riparian impacts
- Restore Administrative Facilities
- Reduce long-term impacts of road on river flood plain and fisheries
- Reasonable capital costs
- Least vulnerable action alternative to future flood events
- Lowest O&M costs
- Constructability



#### Compliance

- Environmental Assessment released to public November 2019.
- Expected FONSI March 31, 2020
- On-going consultation and coordination with LEKT, SHPO, NMFS and USFWS
- Permitting by FHWA

### Schedule

Activity	Date
Decision Document (FONSI)	March 2020
Permits	March 2021
Design Complete	April 2021
Construction Award	June 2021
Begin Construction	July 2021
In water work (Diversion)	Early August 2021*
Construction Complete	October 2023

<sup>\*</sup> In water work is best in late July/early August

# Thank You Questions?





