

Chapter 6 - Treatment Plan

Introduction

1 This chapter presents the treatment plan for
2 the preservation, repair, and stewardship
3 of the archeological landscape of Hopewell
4 Culture National Historical Park. An
5 evaluation of alternatives by NPS staff was
6 conducted during a work session in May
7 2015 and the preferred alternative was
8 refined through a series of work sessions.
9 Alternative 2 was identified as the preferred
10 alternative and represents the NPS preferred
11 management action.

12
13 This chapter presents a detailed description
14 and implementation of the preferred
15 alternative (Alternative 2). The narrative and
16 graphics presented in this chapter reflect the
17 desired future condition of the archeological
18 landscape.

19
20 The treatment plan emphasizes the
21 Hopewell Culture, revealing the grand scale
22 and monumentality of the Hopewellian
23 constructions, and interpretation of their
24 unique lifestyle. The archeological landscape
25 will be rehabilitated to depict the story
26 of earthwork creation and lifeways of the
27 Hopewell people within their geological
28 and ecosystem context. The treatment
29 plan protects the archeological resources,
30 provides a rich visitor experience, and
31 fosters continued archeological research
32 and investigations. This treatment plan is
33 compatible with the GMP and Long-Range
34 Interpretive Plan.

35
36
37
38
39
40
41
42
43
44

Treatment Approach

1 This plan recommends a rehabilitation
2 approach for three of the earthwork
3 complexes: Mound City Group, Hopewell
4 Mound Group, and Seip Earthworks, and
5 a preservation approach for Hopeton
6 Earthworks and High Bank Works. This
7 approach provides for the long-term
8 management of the archeological landscape
9 and focuses on preserving and protecting
10 contributing features while providing a
11 holistic visitor experience.

12
13 Rehabilitation and preservation are the
14 appropriate treatment approaches for the
15 Hopewell Culture NHP. The park has a long
16 period of significance, has undergone few
17 modifications, and has integrity in location,
18 setting, materials, workmanship, feeling,
19 and associations. A rehabilitation approach
20 allows new additions which range from
21 visitor orientation to trails, to marking or
22 rehabilitation of select archeological features.
23 Actions allowed under rehabilitation include
24 stabilization, preservation, and repair. The
25 visitor experience suffers from the fact that
26 most of the mounds and earthworks are very
27 difficult to see today because of plowing and
28 other surface impacts. Rehabilitation permits
29 a variety of treatments that can serve to
30 make the primary resources more visible and
31 enhance visitor experience.

32
33 Although rehabilitation is the overall
34 treatment approach, the application of the
35 treatment is individualized based on the
36 specific characteristics of the earthwork
37 complex. At all park units, extant below- and
38 above-grade archeological features will be
39 preserved.

40
41 At Mound City Group, previously
42 reconstructed mounds will be preserved
43 and previously unreconstructed mounds
44 and borrow pits have the opportunity to be

1 marked and rehabilitated. The treatment of
2 Mound City Group maintains this park unit
3 as the main visitor orientation area, however
4 non-contributing features such as the visitor
5 center, and administrative and maintenance
6 buildings will be removed from the immediate
7 setting. This will focus visitor attention and
8 respect towards the earthwork complex.
9 Circulation routes will echo the spatial
10 organization of the earthwork complex, and
11 views to adjacent properties will be screened,
12 focusing the experience inward.
13
14 Preservation at Hopeton Earthworks focuses
15 on the protection of extant resources
16 and allows the park unit to be a focus for
17 archeological research. The desired outcome
18 for the landscape is for the entire earthwork
19 complex and adjacent setting to be protected
20 and preserved. This includes acquisition
21 of adjacent properties that are negatively
22 impacting archeological resources and
23 distract from the setting, and reinterpreting
24 the area as a Hopewell ceremonial site. The
25 park unit will become accessible to visitors,
26 with a new parking area and trails that allow
27 for understanding of the earthworks.
28
29 At Hopewell Mound Group, rehabilitation
30 emphasizes revealing the spatial qualities
31 of the Great Enclosure. Existing large scale
32 intrusions, including utilities, structures,
33 and other non-contributing features that
34 do not reflect the Hopewellian earthwork
35 complex will be removed and/or relocated.
36 Archeological features will be potentially
37 marked to increase visibility and new visitor
38 trails will further emphasize the monumental
39 earthwork complex.
40
41 Rehabilitation at Seip Earthworks includes
42 preservation of previously reconstructed
43 archeological features, and allowing
44 for marking of features that are not

1 currently visible. The full extent of the
2 earthwork complex will be preserved,
3 which includes property acquisition, and
4 removal of the current visitor parking
5 area, and non-contributing features that
6 have been constructed on top of, or close
7 to archeological features. A new visitor
8 parking area will be located on an adjacent
9 property, with pedestrian routes allowing for
10 exploration of the earthwork complex.
11
12 Preservation is the treatment approach at
13 High Bank Works, and focuses on protection
14 of the entire earthwork complex. This will
15 require acquisition of private inholdings,
16 particularly at the Parallel Walls. High Bank
17 Works will be a focus for archeological
18 research, while also allowing visitor access.
19 Pedestrian routes will connect across the
20 earthwork complex, and interpretation will
21 focus on the construction of the archeological
22 features and their astronomical alignments.
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44

Study Area

1 The treatment recommendations for
2 the study area guide the preservation
3 and rehabilitation of the archeological
4 landscape of Hopewell Culture NHP. These
5 recommendations offer guidance for the park
6 holistically with measures for preserving
7 extant features and qualities, and methods
8 for rehabilitating contributing features
9 associated with the study area as a whole.

10
11 Treatment recommendations for the
12 study area are presented for six landscape
13 characteristics: Natural Systems and Features,
14 Spatial Organization/Topography/Views,
15 Land Use, Archeological Features, Circulation,
16 and Vegetation.

17 **Natural Systems and Features**

18 Treatment recommendations for natural
19 systems and features include preserving
20 and protecting the native ecology of rivers,
21 streams, plants, and wildlife.

- 22
23
24 1. Preserve extant native vegetation and
25 wildlife habitat.
26
- 27 2. Protect riparian corridors of the Scioto
28 River, Paint Creek, and North Fork Paint
29 Creek. Maintain and repair riparian
30 vegetation, and mitigate damage from
31 erosion, pollution, and invasive species.
32
- 33 3. Work with adjacent land owners and local
34 and regional partners to protect areas of
35 important natural vegetation and views of
36 the Appalachian Plateau foothills.
37
- 38 4. Integrate and interpret the Scioto River
39 valley and natural systems as part of the
40 visitor experience.
41
42
43
44

1 **Spatial Organization/Topography/Views**

2 Treatment recommendations for the study
3 area for the spatial organization focus on
4 reestablishing the connection between the
5 earthwork complexes to the river and hills
6 largely by establishing views between these
7 features.
8

9 The other focus is for the individual
10 earthwork complexes to be perceived as their
11 original discrete spaces, separate from visitor
12 or administrative and maintenance areas. The
13 form, alignment and relationships between
14 archeological features of each earthwork
15 complex will be reestablished.

- 16
17 1. Reestablish spatial connections between
18 the earthwork complexes and their
19 adjacent waterways by reestablishing
20 views and by adding trails.
21
- 22 2. Preserve natural topography created by
23 river morphology to the greatest extent
24 possible. Work with local agencies and
25 partners on river management.
26
- 27 3. Locate new facilities to not interfere with
28 the spatial organization of the earthwork
29 complexes.
30
- 31 4. Reestablish wooded areas along banks
32 of waterways and at the edges of the
33 earthwork complexes. Wooded edges
34 will serve as a screen for adjacent
35 development. Buffer zones are needed
36 to protect the setting, and are important
37 for establishing and maintaining World
38 Heritage Site status.
39
- 40 5. Spatially depict each earthwork complex
41 to express the original mass, form, and
42 scale of the original spaces. Rehabilitate
43 the spatial orientation between each
44 earthwork complex and the surrounding

natural landscape to reflect the original relationships between earthwork complexes to rivers and hills. Work with adjacent land owners to protect views and provide visual buffers of adjacent development.

Land Use

Treatment recommendations for land use include protection of property where earthwork complexes are known to occur, and protection of adjacent areas that enrich the cultural landscape setting. Partnerships and land trusts will be established in order to preserve archeological resources and to protect the earthwork setting by establishing buffer zones around the park units. When necessary, the park may explore the acquisition of land outside of legislated boundaries by willing sellers only, following congressional action. Adjacent properties to preserve through partnerships or acquisition include:

- Hopeton Earthworks. The boundary will be expanded to the north and west, to the Scioto River. The NPS will work with adjacent land owners to protect archeological resources and provide visual protection for the earthwork setting. Additional land or easements will be necessary to connect to Mound City Group with a bridge across the Scioto River.
- Hopewell Mound Group. The boundary on the south at will be extended to North Fork Paint Creek. The NPS will work with adjacent land owners to protect these lands or purchase the land from willing sellers in order to protect significant archeological resources and to provide visual protection from future residential development.

- Seip Earthworks. Agreements with adjacent land owners will be explored to protect the whole of the earthwork complex and provide a buffer between the cultural landscape and adjacent development. Landscape buffers are desirable at Paint Creek on the west and south sides, and to the east past Dill Road to the east of Paint Valley High School. From the creek, a northern buffer is needed that will follow U.S. Highway 50 to the edge of the Paint Valley High School property. A cooperative agreement or easement will be needed to provide visitor parking and access to the park unit from the high school property.

- At High Bank Works, agreements with adjacent land owners will be explored in order to protect the entirety of the earthwork. The goal is to join the two discontinuous properties, in order to include the entire earthwork complex and to provide access to the Scioto River. Potential agreements or property acquisition will include land to the west of the Large Circle to the edge of the upper river embankment; the Parallel Walls; and west to the edge of the Scioto River. An easement will be necessary to provide access across the railroad tracks, and to provide access to private land on the lower river terrace.

Archeological Features

The treatment plan provides for the preservation, maintenance, and repair of all archeological features. General recommendations for the treatment of archeological features are presented in this section. The individual earthwork complex descriptions provide more detailed recommendations.

A summary of acceptable treatments is provided as a matrix "TABLE 6-1. Features

-
- 1 Treatment Matrix". The matrix indicates
2 the preferred and optional treatment for each
3 archeological feature, by earthwork complex.
4 "ILLUSTRATION 6-1 Implementation Choices"
5 graphically depicts each treatment choice.
6
- 7 1. Investigations and Research. Further
8 research will continue to be a focus for
9 the study area, which has the potential to
10 reveal a vast amount of information about
11 the Hopewell.
12
- 13 a. Additional archeological work is
14 needed to elucidate the nature
15 of the occupation of the area and
16 reveal information on the life of
17 early peoples and the creation of the
18 earthwork complexes.
19
- 20 ° Conduct further archeological
21 research to better understand the
22 Hopewell Culture.
23
- 24 ° More research is needed to reveal
25 the daily lifestyle of the Hopewell
26 Culture including regional settlement
27 patterns, rituals, use of earthwork
28 complexes, trade routes, and
29 subsistence, etc. Little is known of
30 early American Indian habitation
31 sites in relationship to the earthwork
32 complexes, and modes of circulation
33 (waterways and overland routes)
34 between earthwork complexes.
35
- 36 b. Undertake measures to identify
37 and preserve areas of potential
38 archeological significance.
39 Archeological investigation will be an
40 on-going process, and the scope of
41 archeological work will be expanded.
42
- 43 c. Additional archeological research,
44 investigations, and magnetic surveys
45 are needed to locate undocumented
46 archeological resources, especially for
portions of earthwork complexes that
remain on private property.
- d. Additional archeological studies are
needed to confirm the accuracy of
reconstructions.
- ° Additional research, investigations,
and surveys are needed to
confirm material reconstructions
and to better understand the
construction methodology of the
Hopewellian earthwork complexes.
Reconstructions of mounds and
earthen walls may not have been built
with materials that match the original
materials in the original compositions.
- e. Radiocarbon dating, pollen
and phytolith analysis, soil
micromorphological analysis, etc. may
reveal historic vegetation patterns.
- f. Undertake archeological
investigations for any proposed
improvements that could impact
above- or below-grade archeological
resources in advance of any work.
Integrate archeological investigations
with any and all construction
activities.
- ° Include archeological monitoring
when undertaking improvements
(including trail construction) to
identify potential archeological
resources.
- ° Excavation of any type within
Hopewell Culture NHP will occur
only with consultation with the
park archeologist and the Midwest
Archeological Center.
2. Best Practices - Preservation of Features.
The vision for the archeological features

TABLE 6-1. Features Treatment Matrix

| | Choice A | Choice B | Choice C | Choice D |
|---|----------|----------|----------|----------|
| Mound City Group | | | | |
| Previously Reconstructed Mounds (Mounds 1 through 23) | P | O | N/A | N/A |
| Mounds X1 & X2; 24 & 25 | O | O | P | N/A |
| Enclosure (interior space) | P | O | N/A | N/A |
| Enclosure Walls | P | O | N/A | N/A |
| Borrow pits | P | O | N/A | N/A |
| Large Mounds (1, 2, 3, 4, 5, 7, 8, 18) | O | O | N/A | P |
| Hopeton Earthworks | | | | |
| Great Circle | O | P | N/A | N/A |
| Square Enclosure | O | P | N/A | N/A |
| Parallel Walls | O | P | N/A | N/A |
| Circle A | O | P | N/A | N/A |
| Circle B | O | P | N/A | N/A |
| Circle C | O | P | N/A | N/A |
| Mounds (3) | O | P | N/A | N/A |
| Borrow pits | O | P | N/A | N/A |
| Enclosure Interiors | O | P | N/A | N/A |
| Hopewell Mound Group | | | | |
| Great Enclosure | O | O | P | N/A |
| Square Enclosure | O | O | P | N/A |
| D-shaped Enclosure | O | O | P | N/A |
| Great Circle | O | O | P | N/A |
| Mounds (5 verified) | O | O | P | N/A |
| Mounds (33 unverified) | O | P | O | N/A |
| Ditches | O | P | O | N/A |
| Enclosure Interiors | O | P | N/A | N/A |

P = Preferred

O = Optional

| | Choice A | Choice B | Choice C | Choice D |
|------------------------|----------|----------|----------|----------|
| Seip Earthworks | | | | |
| Large Circle | O | O | P | N/A |
| Seip-Pricer Mound | O | O | N/A | P |
| Seip Conjoined Mound* | O | O | N/A | P |
| Small Circle | O | O | P | N/A |
| Large Square | O | O | P | N/A |
| Borrow pits | O | P | O | N/A |
| Enclosure Interiors | O | P | N/A | N/A |
| High Bank Works | | | | |
| Great Circle | P | O | N/A | N/A |
| Octagon | P | O | N/A | N/A |
| Parallel Walls | P | O | N/A | N/A |
| South Earthwork | P | O | N/A | N/A |
| Borrow pits | P | O | N/A | N/A |
| Enclosure Interiors | P | O | N/A | N/A |

P = Preferred

O = Optional

*Optional: consider rehabilitating the feature if adequate documentation exists and if it assists in protecting resources and improving visitor experience.




ILLUSTRATION 6-1 Implementation Choices

is preservation of all extant archeological features. Using best practices, the earthwork complexes will be cleared of any woody vegetation and repaired as necessary. Generally, visitor access will not be allowed on the earthwork complexes.

a. Preserve all extant below- and above-grade archeological features. Stabilize and repair archeological features as needed.

° Repair scars with clean, artifact and weed-free fill dirt.

° Use a barrier fabric to separate potential archeological artifacts and fill.

b. Remove undergrowth and trees on archeological features, taking measures to preserve the below- and above-grade features.

° Cut trees and undergrowth. Do not forcibly remove roots as this might damage below-grade archeological features.

° Maintain earthwork complexes free of trees and shrubs.

c. Protect archeological features from erosion. Control stormwater runoff and reduce sediment within borrow pits.

d. Protect archeological features from animal burrowing, repairing damage as necessary.

e. Remove non-contributing features from the earthwork complexes.

f. Monitor stream banks of the Scioto River, Paint Creek, and the North Fork Paint Creek for erosion that threatens archeological resources, and stabilize as necessary.

3. Rehabilitation of Archeological Spaces.

Rehabilitate archeological spaces to reveal their mass, form and scale.

a. Discontinue cultivation in the archeological landscape.

b. Use a low growing grass mix (<6 to 12 inches in height) across the entire archeological space to create a consistent cover. Maintain this grass mix by mowing several times per season. The aesthetic should be an open space of mown grasses at differing heights, that assists in the visibility of the earthworks.

° Use a taller grass / herbaceous mix at the edges of the earthwork complexes to distinguish these from the surrounding landscape.

c. Preserve areas of archeological scatter.

° Discontinue cultivation in areas of known or potential archeological scatter.

° Use a grass / herbaceous mix as a consistent groundcover in these areas, mown a few times per year.

° If archeological investigations are imminent, either mow the grass / herbaceous mix more frequently to maintain a lower cover, or plant the area with a low grass mixture and mow more frequently.

4. Rehabilitation of Archeological Features.

In some locations, rehabilitation of archeological features is recommended. This may include creating three-dimensional depictions using new soil or a cobble cover, or the use of vegetation.

a. Rehabilitation of archeological features may only be considered at such time as adequate documentation is available to ensure authenticity. This may include magnetic surveys or other non-invasive methods to accurately locate features, and/or archeological excavations to verify dimensions, materials, etc.

b. Potential markings or rehabilitation techniques must be further researched to fully understand potential impacts on below-grade archeological features.

c. The marking / rehabilitation illustrated and described herein shows the maximum extent of change considered appropriate. The implementation of these recommendations may be applied in a gradual approach that may or may not result in application of the full extent of the recommendations.

d. With adequate documentation, rehabilitate archeological features using these techniques (ILLUSTRATION 6-1).

Vegetation

Use vegetation to depict, mass, scale, and form of features.

- ° Choice A: Use a grass mix for the archeological features and archeological spaces maintained at a low height (< 6 inches). At the edge

of the space (typically an earthen wall) begin plantings of taller grasses and herbaceous species to delineate the mass and scale of the earthwork complex.

- ° Choice B: Use a low growing grass mix (6 -12 inches height), allowing the grass to grow taller on mounds, earthen walls, and borrow pits than in surrounding archeological areas.

Earthen Markings

Rehabilitate archeological features that are not visible above-grade by creating a new earthen feature.

- ° Use clean, artifact and weed free fill dirt, separated by a barrier fabric to distinguish new material from old.

- ° Base the form, height and mass of the rehabilitation on current scholarship.

- ° Plant new archeological features with a grass species to match adjacent features.

Cobble Markings/ Cobble Cover

Rehabilitate select mounds with a stone cobble cover, as existed during the period of significance.

- ° Cover visible mounds with a new cobble layer (< 12-inches), to indicate the edges and three-dimensional form of the mound.

Circulation

Treatment recommendations for the study area circulation emphasize improved connections and wayfinding between the park units, and encouraging alternative transportation.

1. Vehicular Circulation. The vehicular circulation system within the study area will remain similar to the existing system. Modifications will include relocation of visitor and administration and maintenance facilities, requiring vehicular circulation to be relocated as well.

2. Pedestrian Circulation. Pedestrian connections are needed to link the earthwork complexes and to interpret overland and waterway routes that may have been used by the Hopewell people.

a. An interconnected water route will be created to connect the park units, and an enhanced trail network will provide better pedestrian and bicycle access (overland routes).⁶⁻¹

b. Re-connect the earthwork complexes to the rivers and streams by creating an interconnected water route between all park units. This will include making river courses accessible by canoe and kayak access at select locations.

c. Work with Ross County Park District and partners in their efforts to establish a greenway trail system that links the earthwork complexes. This could tie into the Tri-County Trail System. NPS will add trail connections, bicycle racks, and directional signs.



Figure 3-1. Example of a Cobble Marking, at Fort Ancient Archeological Park, Ohio.

d. Work with Ross County Park District in their efforts to establish bike paths along roads and along abandoned railways.⁶⁻²

e. Work with partners to connect Mound City Group and Hopewell Mound Group with a bike path along state road 104 to the Tri-County Triangle Trail, or a route through the Veterans Affairs medical Center and Pleasant Valley Wildlife Area to the Tri-County Triangle Trail.⁶⁻³

f. Coordinate with Ross County Park District, City of Chillicothe, and Ohio Department of Natural Resources to locate, design, and construct canoe launches and access trails at each earthwork complex.⁶⁻⁴

g. Work with the Chillicothe Transit Company to establish a scheduled bus route system to each earthwork complex.⁶⁻⁵

6-1 NPS, Hopewell NHP General Management Plan, 24.

6-2 NPS, Hopewell NHP General Management Plan, 26.

6-3 NPS, Hopewell NHP General Management Plan, 26.

6-4 NPS, Hopewell NHP General Management Plan, 26.

6-5 NPS, Hopewell NHP General Management Plan, 26.

| | | | |
|----|--|----|---|
| 1 | h. Within each earthwork complex, the | 1 | resources or archeological research |
| 2 | pedestrian circulation system will be | 2 | including geophysical surveys would |
| 3 | improved by adding routes that allow | 3 | not be negatively impacted. |
| 4 | for understanding of the earthworks. | 4 | |
| 5 | | 5 | |
| 6 | Vegetation | 6 | e. Vegetation within the earthwork |
| 7 | Treatment recommendations for the study | 7 | complexes will be low (3" to 12") |
| 8 | area are to manage vegetation to preserve | 8 | and periodically mown. Tall grasses |
| 9 | the earthwork complexes, to distinguish | 9 | (greater than 12") create habitat for |
| 10 | visitor, administration, and maintenance | 10 | destructive burrowing animals such |
| 11 | facilities from the earthwork complexes, | 11 | as groundhogs, and make it difficult to |
| 12 | and to retain and manage native vegetation | 12 | monitor archeological landscapes for |
| 13 | along waterways and in areas outside | 13 | the presence of destructive burrowing |
| 14 | archeologically sensitive areas. | 14 | animals. |
| 15 | | 15 | ° In areas inside the earthwork |
| 16 | 1. Vegetation types and management | 16 | complex where frequent mowing |
| 17 | techniques will be used to preserve the | 17 | will take place, there is little point in |
| 18 | archeological landscape, assist in framing | 18 | seeding plant species with wildlife |
| 19 | views, and to screen adjacent land uses. | 19 | benefit. Here the best choice should |
| 20 | | 20 | center on sustainability, drought |
| 21 | a. Discontinue agricultural cultivation | 21 | tolerance (especially considering the |
| 22 | within archeological landscapes. This | 22 | expectation of summers getting hotter |
| 23 | practice has degraded archeological | 23 | and drier) and durability to foot traffic |
| 24 | features over time, leaving many | 24 | and mowing equipment. Consider |
| 25 | features indiscernible. | 25 | a low-maintenance turf mix that is |
| 26 | | 26 | naturally short and slow-growing and |
| 27 | b. Remove dead and dying trees within | 27 | requires less-frequent mowing, such |
| 28 | the enclosures. Plant new trees for | 28 | as a mix that contains several cultivars |
| 29 | visitor shade only after archaeological | 29 | of fescue. ⁶⁻⁶ |
| 30 | research is completed to demonstrate | 30 | |
| 31 | these will not adversely impact | 31 | f. Avoid tall grasses and shrubs within |
| 32 | archaeological resources. New | 32 | the earthworks, which limit access |
| 33 | plantings should be minimal so they | 33 | for archeological research, especially |
| 34 | do not interfere with the spatial | 34 | the new generation of large-scale |
| 35 | organization of the earthwork | 35 | geophysical survey instruments, |
| 36 | complex. | 36 | which require low, mown vegetation |
| 37 | | 37 | for data collection. |
| 38 | c. Test and evaluate machinery used | 38 | |
| 39 | for landscape management to ensure | 39 | g. Remove heavy brush and woody |
| 40 | maintenance practices will not impact | 40 | vegetation from archeological |
| 41 | archeological features. | 41 | features, as this may be damaging |
| 42 | | 42 | resources. |
| 43 | d. Burning would be allowed as a | 43 | |
| 44 | vegetation management tool after | 44 | |
| 45 | sufficient research is completed | 45 | |
| 46 | to demonstrate that archeological | 46 | |

⁶⁻⁶ Personal communication, Dafna Reiner, Hopewell Culture NHP Biologist; 5/23/2015.

h. Some large trees may be retained or planted for visitor shade within the earthwork area after sufficient archaeological research is completed to demonstrate these will not adversely impact archaeological resources.

i. Remove vegetation for safety reasons, such as hazardous trees, and to eradicate invasive exotic species, in a manner that protects archeological resources.

j. Add vegetation to assist in distinguishing archeological features from non-features. Use vegetation to reveal mounds, walls, and borrow pits.

k. Maintain a distinct vegetation type on archeological features that is different from that used in visitor and administrative areas.

2. Maintain a mix of native herbaceous species, mown 1 to 2 times per year, in areas outside and adjacent to the earthwork complex.

° Refer to six seed mixes that are researched, documented, and proven.⁶⁻⁷ Choose management techniques that will favor native biodiversity.

° Choose management techniques that will favor native biodiversity.”

⁶⁻⁷ Personal communication, Dafna Reiner, Hopewell Culture NHP Biologist; 5/23/2015. See, Stubbendiek, James and Cheryl D. Dunn. *Hopewell Culture National Historical Park: Review of the Literature on the Influence of Roots on Archeological Features and Vegetation Restoration Recommendations*. (Lincoln: University of Nebraska, 2011).

3. Manage the woodland vegetation surrounding the earthwork complex. Maintain a healthy tree cover, free of invasive, exotic species.

4. Manage the vegetation associated with the waterways to preserve the native riparian vegetation along the river terraces.

Small Scale Features

Small scale features will play a minor role and will not distract from the archeological landscape.

1. Further investigation is needed to evaluate into the significance of some small scale features.

a. Those that are found to be non-contributing and do not serve an active role in interpretation of the earthwork complex will be removed.

2. Any new small scale features will be minimal and unobtrusive.

a. Design and situate new small scale features such as signs and interpretive panels, to be low-profile and unobtrusive.

3. Improve interpretation of the earthwork complex and cosmology.

4. Use alternative media to provide visitors with access to large amounts of research and documentation of archeological features—keyed to specific locations—to enhance visitors’ understanding of the authenticity of the earthwork complexes.

a. Explore ways to enhance interpretation, including electronic (possibly interactive) representations of what the earthwork complexes may have looked like.

Best Management Practices

1 The following is a list of best management
2 practices and methodologies for the care of
3 the cultural landscape. The best management
4 practices are derived from current practices
5 for earthworks preservation from the U.S. and
6 abroad, and provide a context for decision
7 making.

8 **General**

10 1. Monitoring archeological sites for
11 damage and condition is essential
12 site management. Maintain a periodic
13 assessment of specific management issues
14 and the general state and conditions of
15 the archeological site.

16
17 a. Monitoring methods include visual
18 assessment; qualitative scoring (good,
19 fair, poor condition); fixed position
20 photography (annual, bi-annual)
21
22 b. Inspect mounds periodically for signs
23 of erosion, illegal tampering, or other
24 damage.

25
26 2. Protect earthworks from erosion by
27 preventing erosion scars. As soon as
28 erosion develops, any scars need to be
29 dressed with soil and re-seeded.

30
31 3. Ensure positive drainage away from
32 archeological resources. The land
33 drainage system should prevent surface
34 waterlogging and the silting up of
35 features. Standing water can damage
36 features below-grade.

37
38 4. Any new utilities should be located away
39 from the archeological sites. Irrigation
40 lines should not be installed within any
41 archaeological site.

42
43 5. Signs, barriers, fences, etc. should be
44 movable (i.e., should not extend into

1 the ground which would disturb below-
2 grade features). Place fences way from
3 archeological sites. Fence posts, signs,
4 utility poles, etc should not be placed in or
5 on archeological features.

6
7 6. Exterminate wildlife burrowing into, or
8 adjacent to, known archaeological features;
9 block up burrow entrances.

10
11 7. For erosion control, revet with sandbags,
12 boarding or geotextile fabric while re-
13 establishing groundcover.⁶⁻⁸

16 **Repair and Reconstruction**

17 1. The Wisconsin Department of Natural
18 Resources recommends the following
19 for mound site repairs and restoration.⁶⁻⁹
20 Before proceeding, restoration requires
21 extensive consultation. A general
22 recommended procedure includes the
23 following steps:

24
25 a. Record the nature and extent of
26 damage and current mound condition;

27
28 b. Remove leaf litter from the damaged
29 area;

30
31 c. Lay geotextile fabric on the ground
32 surface in the area of damage;

33
34 d. Use hand tools to place new artifact-
35 free soil from an off-site location on
36 the fabric to replace missing soil.
37 Compact new soil by hand to match
38 the contour of the existing mound or
39 wall;

41 ⁶⁻⁸ Hadrian's Wall World Heritage Site, UK

42 ⁶⁻⁹ Wisconsin Department of Natural Resources, "Burials,
43 Earthworks, and Mounds Preservation Policy and Plan;"
44 Wisconsin Department of Natural Resources, "Woody
45 Invasive Vegetation Removal and Site Restoration,"
Aztalan State Park, August 7, 2013; and Effigy Mounds
National Monument Cultural Landscape Report.

- e. Soil should be obtained from an area well away from the mounds or other archeological site;
- f. Do not apply chalk or lime to the ground surface to outline mounds or mound damage. Do not place contemporary objects within new soil.

2. Repair of earthworks due to animal damage, per UK recommendations.⁶⁻¹⁰

- a. Block animal burrows with turf, earth, sand, or gravel;
- b. Remove animal burrows by raking or harrowing, then reestablish vegetative cover.

3. After removal of a tree from an archeological feature, flush cut or mechanically grind the remaining portion of the trunk and stump to grade. As needed, regrade the area with soil that matches the parent soil as closely as possible in texture and composition. Use a manual tamper to gently compact the soil in the hole. Apply desired seed mix, a tackifier, fiber-mulch and, if needed a natural organic fertilizer, to enhance post germination growth. Use a fertilizer with a low salt index to minimize adverse effects on archeological resources. In areas subject to erosion, lay an erosion control blanket, made of natural materials so that it will decompose, over the disturbed site. Tack the material in place to prevent it from being shifted.⁶⁻¹¹

4. If there has been damage due to falling limbs, or other occurrences that have

⁶⁻¹⁰ Hadrian's Wall World Heritage Site, UK

⁶⁻¹¹ NPS, How to Preserve Earthworks, Case Studies for Emergency Stabilization: http://www.nps.gov/tps/how-to-preserve/currents/earthworks/case_studies.htm

created holes or depressions in the earthwork, cover the impact depression on the earthwork with a 2" layer of sand. The sand will serve as a tracer layer, similar to that used adjacent to underground utilities, to inform future excavations that there was ground disturbance at that depth. Fill the remaining portion of the depression with soil that matches the parent soil as closely as possible in texture and composition (texture, % sand/silt/clay, % organic matter, fertility, etc.). Use a manual tamper to gently compact the soil into the depression.⁶⁻¹²

Circulation

1. Vehicles should not be driven onto mounds or burial sites. Walking on mounds should be avoided, and trails, roads, and paths should clearly visible and situated to avoid mound or burial sites.
2. Create a single permanent route, rather than many routes.⁶⁻¹³ Conversely, utilize movable interpretation panels that allow routes to alter in order to reduce wear and erosion.⁶⁻¹⁴
3. Do not drive vehicles across archeological sites in wet weather.
4. Minimize walking on all earthworks, as a preservation issue as well as respect for the builders and the Hopewell people.⁶⁻¹⁵

⁶⁻¹² NPS, How to Preserve Earthworks, Case Studies for Emergency Stabilization: http://www.nps.gov/tps/how-to-preserve/currents/earthworks/case_studies.htm

⁶⁻¹³ Farming the Historic Landscape, Caring for Archaeological Sites in Grassland, English Heritage, UK: 2004

⁶⁻¹⁴ Hadrian's Wall World Heritage Site, UK

⁶⁻¹⁵ Ohio Historical Society recommendations, Newark Earthworks State Memorial

5. At Wisconsin State Parks (numerous effigy and burial mounds including Aztalan State Park), trails are located a minimum of 5' from the base of the mound or mound group. A trail does not need to be built to provide access to every mound in a group. Wood chips, shredded bark, or mowing are used for trail maintenance.

Vegetation

Establishing vegetation / Seed mixes.

Choose management techniques that will favor native biodiversity. Newly acquired agricultural fields should be planted in tall native grassland vegetation, favoring high biodiversity mixes where appropriate in light of considerations including long-term maintenance and weed pressure. Mounds and earthworks at other archeological sites in the U.S. are typically planted with a combination of natural and planted grasses, which are mown periodically or burned.⁶⁻¹⁶

1. There are three maintenance regimes that can be followed. Mowing is by far the most popular, with prescribed burning being an option where native grasses are dominant and the surrounding community allows it, or grazing, which has been successfully used in Europe but has not been a technique adopted in the United States.⁶⁻¹⁷

- a. The most popular management strategy for interpreted earthworks is a grass or herbaceous cover that is free of woody species. Well-protected earthworks found with this cover exhibit a healthy, continuous carpet of grasses and herbaceous plants. Bare spots, gouges from careless maintenance practices, animal burrows, and invasive exotic

vegetation, which potentially threaten earthworks, should be avoided.⁶⁻¹⁸

2. Establishing grassland. It is desirable to select a cover seed mix in which natives dominate. Refer to six seed mixes that are researched, documented, and proven.⁶⁻¹⁹

- a. When re-seeding grassland, use minimal cultivation techniques, such as hydroseeding, slit seeding, direct drilling, sodding, and hand-seeding.⁶⁻²⁰
- b. In areas inside the earthwork complex where frequent mowing will take place, there is little point in seeding plant species with wildlife benefit. Here the best choice should center on sustainability, drought tolerance (especially considering the expectation of summers getting hotter and drier) and durability to foot traffic and mowing equipment. Consider a low-maintenance turf mix that is naturally short and slow-growing and requires less-frequent mowing, such as a mix that contains several cultivars of fescue.⁶⁻²¹
- c. Consult a native plant specialist to determine an appropriate seed mix for the area and the unique cultural requirements of the selected mix, including soil pH, sowing season, appropriate application technique,

⁶⁻¹⁸ Shaun Eyring and Lucy Lawliss editors, Sustainable Military Earthworks Management; NPS Currents, 1998; <http://www.nps.gov/tps/how-to-preserve/currents/earthworks/assess.htm>

⁶⁻¹⁹ Personal communication, Dafna Reiner, Hopewell Culture NHP Biologist; 5/23/2015. See, Stubbendiek, James and Cheryl D. Dunn. *Hopewell Culture National Historical Park: Review of the Literature on the Influence of Roots on Archeological Features and Vegetation Restoration Recommendations*. (Lincoln: University of Nebraska, 2011).

⁶⁻²⁰ Farming the Historic Landscape, Caring for Archaeological Sites in Grassland, English Heritage, UK: 2004

⁶⁻²¹ Personal communication, Dafna Reiner, Hopewell Culture NHP Biologist; 5/23/2015.

⁶⁻¹⁶ Wisconsin State Parks; Poverty Point, Louisiana; Etowah, Georgia; Cahokia, Illinois

⁶⁻¹⁷ NPS, Sustainable Military Earthworks Management: www.nps.gov/tps/how-to-preserve/currents/earthworks/imp_manage.htm

and germination period. Use a higher diversity mix where appropriate. Allow for seed mixes to vary, as scholarship evolves.

3. Weeds.

a. The desired character of the landscape is as close to a restored grassland as possible. The park should remove invasive, exotic species as identified by the US Department of Agriculture and the Ohio Department of Agriculture.⁶⁻²² Some exotic species are acceptable, maintained at less than 25 % of cover.

b. Establishing a weed-free seedbed at the initial planting is critical to long-term weed control. More general use of herbicides may be justified at planting and in the first few years to reduce herbicide use over the long term.

c. Control weeds by topping or targeted use of selected herbicides. Apply herbicides selectively with spot treatments, spraying specific small problem areas, or applying herbicide to individual plants with a wick applicator.

4. Mowing.

a. Mowing dates have a pronounced effect on the growth of different grasses and affect bird nesting habitat. Mow both cool-season and warm-season grasses in late winter or early spring. Mowing at this time

lays down organic mulch in the form of grass clippings, which helps in erosion control. Do not mow sites after early to mid-July that are covered predominantly by native warm-season grasses or where native grasses are being encouraged. This permits full development of the leaves and flowering stalks followed by seed maturation, which typically occurs in October.

b. In general, when native grasses are the desired dominant species on earthworks, allow the grass to grow at least ten to twelve inches between mowing and set the minimum mower height at six inches.⁶⁻²³

c. When earthworks are mown, care should be taken to avoid damage by raising the blade of the mower. Avoid mowing while soil is wet, and use a hand mower or low impact tires if possible.⁶⁻²⁴

d. Test and evaluate machinery used for landscape management to ensure maintenance practices will not impact archeological features.

e. Vegetation outside of the earthworks should be mown once to three times per year after November 1st, determined by the degree of weeds and woody vegetation. Mow only one third to one half every year thereafter, depending on invasion level of woody species. Define areas to be mowed each cycle based on the spatial organization/topography/

⁶⁻²² United States Department of Agriculture, "Federal Noxious Weeds," (USDA: Natural Resources Conservation Service, 2012); and United States Department of Agriculture, "Ohio State-listed Noxious Weeds," (USDA: Natural Resources Conservation Service, 2003).

⁶⁻²³ Shaun Eyring and Lucy Lawliss editors, Sustainable Military Earthworks Management; NPS Currents, 1998; <http://www.nps.gov/tps/how-to-preserve/currents/earthworks/assess.htm>

⁶⁻²⁴ Management Recommendations for Burial Sites, Iowa Office of the State Archaeologist

| | | | |
|----|---|----|---|
| 1 | views of the cultural landscape, with a | 1 | and treating with herbicide to prevent |
| 2 | view toward preserving archeological | 2 | re-growth. Cut material should be |
| 3 | features and enhancing visitor | 3 | disposed of well away from the |
| 4 | experience. | 4 | archeological site. |
| 5 | | 5 | |
| 6 | f. Burning would be allowed as a | 6 | c. Remove brush from the mounds |
| 7 | vegetation management tool after | 7 | annually and haul away from the |
| 8 | sufficient research is completed | 8 | mound area by hand. |
| 9 | to demonstrate that archeological | 9 | |
| 10 | resources or archeological research | 10 | d. Where vegetation is to be thinned |
| 11 | including geophysical surveys would | 11 | for creating or maintaining views, |
| 12 | not be negatively impacted. | 12 | minimize cutting to create narrow |
| 13 | | 13 | views through the forest, capturing a |
| 14 | a. Ideal prescribed burning occurs | 14 | glimpse of the view through trunks of |
| 15 | in March before most bird nesting | 15 | the largest trees. |
| 16 | activity and before peak activity | 16 | |
| 17 | of herpetofauna, however, some | 17 | e. Trees threaten resources due to |
| 18 | mortality is possible. Early Spring | 18 | damage by roots, and wind thrown |
| 19 | burning can also adversely affect | 19 | trees can uproot archeological |
| 20 | insect populations by destroying | 20 | features. |
| 21 | over-wintering eggs, larvae and | 21 | |
| 22 | pupae of insects. This intensity of this | 22 | ° Many earthwork sites have removed |
| 23 | adverse effect is reduced by allowing | 23 | trees from mounds, within the walls |
| 24 | significant adjacent patches of native | 24 | of earthen enclosures, as well as the |
| 25 | grassland to remain unburned. | 25 | area immediately adjacent (within |
| 26 | | 26 | 15 feet) of mounds and earthwork |
| 27 | 5. Removal of vegetation. Remove vegetation | 27 | walls. (examples include Newark |
| 28 | for safety reasons, such as hazardous | 28 | Earthworks, Ohio; Poverty Point |
| 29 | trees, and to eradicate invasive exotic | 29 | World Heritage Site, Louisiana; Angel |
| 30 | species, in a manner that protects | 30 | Mounds State Historic Site, Indiana; |
| 31 | archeological resources. Remove heavy | 31 | Toltec Mounds, Arkansas) |
| 32 | brush and woody vegetation from | 32 | |
| 33 | archeological features, as this may be | 33 | ° Recommend only removing trees if |
| 34 | damaging resources. Avoid tall grasses | 34 | they pose an imminent threat to the |
| 35 | and shrubs within the earthworks, which | 35 | earthworks or if there is an over- |
| 36 | limit access for archeological research, | 36 | riding need to remove the tree for an |
| 37 | especially the new generation of large- | 37 | interpretation, preservation, or access |
| 38 | scale geophysical survey instruments, | 38 | reason. ⁶⁻²⁵ |
| 39 | which require low, mown vegetation for | 39 | |
| 40 | data collection. | 40 | ° Trees and brush should be removed |
| 41 | | 41 | from within 8' of a mound or earthen |
| 42 | a. Removal of woody vegetation and | 42 | wall. Tree cutting is to be done when |
| 43 | extensive clearance should be phased. | 43 | the ground is frozen to reduce damage |
| 44 | | 44 | |
| 45 | b. Removal of vegetation should include | 45 | |
| 46 | cutting stumps close to ground level | 46 | |



⁶⁻²⁵ Ohio Historical Society recommendations, Newark Earthworks State Memorial

to archeological features. Remove trees from mound by cutting by hand down to 6" below ground level and filling the resulting cavity with clean soil, followed by reseeding. This method requires periodic soil filling as the tree decomposes. Alternately, trees may be cut to the ground level and left to decompose naturally.⁶⁻²⁶

Restrict the need for irrigation to small areas or rare occasions such as extreme droughts or plant establishment periods.⁶⁻²⁷

⁶⁻²⁶ Management Recommendations for Burial Sites, Iowa Office of the State Archaeologist
⁶⁻²⁷ NPS, Georgia Trust for Historic Preservation. Guide to Sustainable Earthworks Management, 90% Draft, 1998

Page left intentionally blank.



| |
|---|
| OCTOBER 2015 |
| UNITED STATES DEPARTMENT OF THE INTERIOR HOPEWELL CULTURE NATIONAL HISTORICAL PARK |
| ILLUSTRATION 6-2 |

| | | | |
|---|----------------|---------------|------|
| TITLE OF PROJECT CULTURAL LANDSCAPE REPORT AND ENVIRONMENTAL ASSESSMENT | | | |
| TITLE OF DRAWING STUDY AREA - PREFERRED ALTERNATIVE | | | |
| NAME OF PARK HOPEWELL CULTURE NATIONAL HISTORICAL PARK | | | |
| REGION MIDWEST | COUNTY ROSS | STATE OHIO | 6-21 |

Mound City Group

1 The treatment plan for Mound City Group
 2 emphasizes the interpretation of Hopewell
 3 ceremonialism. The archeological landscape
 4 will be rehabilitated to focus visitor
 5 experience on the creation and use of the
 6 mounds. This will be accomplished through
 7 preservation of the reconstructed mounds
 8 and earthen walls, delineation of previously
 9 unreconstructed mounds, improvements
 10 in circulation routes, removal of damaging
 11 vegetation, and separation between the
 12 visitor orientation area and the ceremonial
 13 landscape. In accordance with the GMP,
 14 Mound City Group will be the mostly highly
 15 developed, and will function as a central point
 16 for park orientation and interpretation.⁶⁻²⁸

17
 18 Rehabilitation is the treatment approach
 19 for Mound City Group. This approach allows
 20 for repair, alterations, and additions while
 21 preserving those features which convey its
 22 historic and cultural significance.

23
 24 Treatment goals for Mound City Group
 25 include the following:

- 26
 27 • Preserve extant above-grade archeological
 28 features.
- 29
 30 • Spatially depict the three-dimensional
 31 earthwork complex.
- 32
 33 • Relocate visitor facilities (building, roads,
 34 parking, etc.) away from the earthwork
 35 complex.
- 36
 37 • Reveal the relationship to the Scioto River
 38 and Hopeton Earthworks.
- 39
 40 • Remove non-contributing features that
 41 impact the archeological landscape.
- 42
 43 • Provide an authentic visitor experience.
- 44

⁶⁻²⁸ GMP, 30.

1 The treatment plan for Mound City Group
 2 illustrates the desired landscape condition
 3 (ILLUSTRATION 6-3).

4 Spatial Organization/Topography/Views

5 The vision for the spatial organization at
 6 Mound City Group is for the forms and
 7 patterns of the archeological landscape to be
 8 visible and viewed without contemporary
 9 intrusions.

10
 11
 12 1. The spatial organization will be
 13 strengthened by removal of non-
 14 contributing features; removal of
 15 vegetation that obscures the earthwork
 16 complex and archeological features;
 17 marking / rehabilitation of non-extant
 18 above-grade mounds and borrow pits;
 19 and rerouting pedestrian circulation
 20 routes to define the spatial qualities of the
 21 earthwork complex.

- 22
 23 a. Complete the spatial depiction of
 24 the three-dimensional form of the
 25 earthwork complex and surroundings
 26 by marking nonvisible archeological
 27 features.
- 28
 29 b. Remove hazardous trees and woody
 30 vegetation that impact or may impact
 31 intact archeological resources.
- 32
 33 c. Remove non-contributing features
 34 from the immediate surroundings of
 35 the earthwork complex, including the
 36 visitor center, park administration,
 37 maintenance, parking, roads, utilities,
 38 etc. Relocate these facilities either off-
 39 site or to less intrusive areas on-site,
 40 away from the earthwork complex.
- 41
 42 d. Maintain a consistent vegetation
 43 type on the archeological features
 44 to distinguish them from visitor and

- | | | | |
|----|---|----|--|
| 1 | administrative areas, and adjacent | 1 | magnetometry or other non-invasive |
| 2 | woodlands. | 2 | archeological techniques. |
| 3 | | 3 | |
| 4 | e. Maintain the enclosed space of the | 4 | b. Evaluate features that may be |
| 5 | earthwork complex by preserving the | 5 | significant in their own right, but that |
| 6 | woodland vegetation surrounding the | 6 | are non-contributing features to the |
| 7 | enclosure wall. The wooded edges | 7 | archeological landscape, including |
| 8 | will also serve as a screen for adjacent | 8 | Camp Sherman remnants. |
| 9 | development. | 9 | |
| 10 | | 10 | 2. <u>Best Practices - Preservation of Features.</u> |
| 11 | f. Add trees and vegetation between the | 11 | Preserve all extant below- and above- |
| 12 | earthwork complex and the adjacent | 12 | grade archeological features. Stabilize and |
| 13 | properties to the west and south to | 13 | repair features as necessary, following |
| 14 | screen the earthwork complex from | 14 | best practices. |
| 15 | these uses. Buffer zones are needed to | 15 | |
| 16 | protect the setting, and are important | 16 | a. Preserve all extant below- and above- |
| 17 | for establishing and maintaining | 17 | grade archeological features. |
| 18 | World Heritage Site status. Work | 18 | |
| 19 | with adjacent land owners to | 19 | b. Preserve and maintain existing |
| 20 | provide visual buffers of adjacent | 20 | reconstructed mounds and the |
| 21 | development. | 21 | earthen walls as contributing features. |
| 22 | | 22 | |
| 23 | g. Create and maintain a view between | 23 | c. Stabilize and repair archeological |
| 24 | the overlook and the river, by thinning | 24 | features as needed, following best |
| 25 | vegetation along a small portion of the | 25 | practices. |
| 26 | riverbank. | 26 | |
| 27 | | 27 | d. Do not allow visitor access on top of |
| 28 | h. Thin vegetation to create a narrow | 28 | the mounds, borrow pits, or earthen |
| 29 | view at the southeast side of the | 29 | walls. |
| 30 | earthwork complex so the Mount | 30 | |
| 31 | Logan Range and the moonrise and | 31 | 3. <u>Rehabilitation of Archeological Spaces.</u> |
| 32 | solstice sunrise alignments can be | 32 | Rehabilitate archeological spaces to reveal |
| 33 | observed. | 33 | their mass, form and scale. Delineate |
| 34 | | 34 | the earthwork complex by markings or |
| 35 | Archeological Features | 35 | rehabilitating archeological features when |
| 36 | The treatment plan recommends | 36 | no discernible topographical relief occurs |
| 37 | preservation and rehabilitation of the extant | 37 | in LiDAR imagery or through visual |
| 38 | and reconstructed archeological features at | 38 | observations. |
| 39 | Mound City Group. | 39 | |
| 40 | | 40 | a. Depict the archeological space of |
| 41 | 1. <u>Investigations and Research.</u> Continue | 41 | the earthwork complex through the |
| 42 | investigations and archeological research, | 42 | following techniques. Use a consistent |
| 43 | including the following research needs. | 43 | palette of materials. |
| 44 | | 44 | |
| 45 | a. Identify currently unknown | 45 | ° Use one consistent vegetation |
| 46 | resources at the outlying areas using | 46 | type and vegetation management |

technique to depict the space of the enclosure and earthwork complex. The aesthetic should be an open space of mown grasses at differing heights that assists in the visibility of the earthworks.

- ° Use a different vegetation management technique for archeological features such as mounds and walls to differentiate between the three-dimensional archeological features and adjacent spaces.

- ° Use a taller grass / herbaceous mix at the edges of the archeological spaces and in areas of archeological scatter, to distinguish these from the surrounding landscape.

- ° Differentiate between the earthwork complex and visitor and administrative / maintenance areas by maintaining distinct vegetation types in the two areas. This can be accomplished by planting a mix of grass species that differs in color and texture, or by maintaining grasses at a different height.

4. Rehabilitation of Archeological Features.

Rehabilitation of non-extant archeological features is recommended. This may include creating three-dimensional depictions using new soil, a cap of stone cobble, or the use of vegetation.

- a. Rehabilitate non-extant archeological features to depict their mass, form and character, as documented by Squire and Davis in 1846, Brown in 2012 and the 2010 magnetic survey, or based upon most recent archeological investigations.

- ° Specific treatment for each archeological feature is provided in ILLUSTRATION 6-3. Cross section examples provided in ILLUSTRATION 6-1 represent examples of applicable rehabilitation techniques.

- b. Use earthen markings to rehabilitate outlines and dimensions of non-extant mounds.

- ° Specific features to be rehabilitated include the following.

- Extra-mural mounds X1 and X2;
- Mounds #24 and #25.

- ° Use a material that differs from the material of the previously reconstructed mounds, to distinguish new material from old.

- ° Where discernible topographical relief occurs, only vegetation or non-permanent markings will be used to delineate features.

- c. Use vegetation to delineate outlines and dimensions of borrow pits.

- ° Protect intact the reconstructed borrow pits and the northeast borrow pit (not reconstructed). Preserve the northeast borrow pit as is, and provide special visitor interpretation to appreciate an intact, authentic, unreconstructed borrow pit.

- ° Reconstruction of the northeast borrow pit would require careful and extensive archeological excavation that should only be excavated after extraordinary justification.

- d. Use a cobble cover to rehabilitate the outlines and dimensions of large, previously-reconstructed mounds.

- ° Specific features to be rehabilitated with cobble cover include the following.

- Mounds #1, 2, 3, 4, 5, 7, 8, 18

- e. Consider marking other archeological features that were part of the ceremonial landscape. This may include charnel houses or other structures that would have accompanied the mounds. These could be marked with simple techniques as listed previously, or temporary installations that could be set up seasonally or for special events.

Circulation

Mound City Group will continue to serve as a primary visitor orientation facility, however the existing circulation system will be modified to add routes that foster understanding of the archeological features and connections to natural features.

1. Vehicular Circulation. The vehicular circulation system will be modified to reroute vehicular parking and access routes to less intrusive locations.

- a. Remove existing entrance drives, visitor and administrative parking areas and vehicular access routes.
- b. Relocate vehicular routes and parking area outside the earthwork complex and screen from view.

2. Pedestrian Circulation. The existing pedestrian circulation system will remain and be improved by adding routes that assist in defining the spatial qualities of the earthwork complex.

- a. Maintain the existing nature trail, and establish as a universally accessible route.

- b. Add a pedestrian trail from the new visitor center and parking area to the earthwork complex.

- c. Establish a trail to follow the edge of the river terrace, north to south, connecting to the existing nature trail.

- d. Establish a loop trail through the North Forty.

- e. Maintain informal access within the enclosure and through the mounds (i.e., no formal trails).

- f. Maintain existing river walk trail with steps, walls, and overlook at the river edge.

- g. Provide access to the river bank, and create a new kayak / canoe access point along the Scioto River.

- h. Create pedestrian routes between Mound City Group and other park units.

- ° Build a pedestrian bridge over the Scioto River and a trail connection to Hopeton Earthworks.

Vegetation

Treatment of vegetation at Mound City Group will focus on preservation of the archeological features. Vegetation will be managed to assist in defining the spatial organization of the earthwork complex, and to frame views and screen adjacent development. Archeological features will be maintained as low, mown vegetation. Vegetation outside the earthwork complex will be managed as tall or woody vegetation.

-
- | | |
|--|--|
| <p>1 1. Vegetation management techniques will</p> <p>2 be used to preserve the archeological</p> <p>3 features.</p> <p>4</p> <p>5 a. Remove trees and woody vegetation</p> <p>6 that impact archeological features</p> <p>7 or diminish the earthwork's spatial</p> <p>8 qualities.</p> <p>9</p> <p>10 ° Maintain the woody vegetation on the</p> <p>11 northeast corner of the enclosure wall</p> <p>12 and Mound #1.</p> <p>13</p> <p>14 ° Maintain existing trees within the</p> <p>15 enclosure. Consider adding trees to</p> <p>16 the enclosure for shade, provided the</p> <p>17 new trees will not negatively impact</p> <p>18 archeological features.</p> <p>19</p> <p>20 b. Reintroduce grasses where trees</p> <p>21 and woody vegetation have been</p> <p>22 removed.⁶⁻²⁹</p> <p>23</p> <p>24 2. Utilize distinct vegetation management</p> <p>25 techniques to reveal the form and spaces</p> <p>26 of the earthwork complex.</p> <p>27</p> <p>28 a. Use a low growing grass mix (<6</p> <p>29 to 12 inches in height) in spaces</p> <p>30 of the earthwork including the</p> <p>31 enclosure, mounds, and borrow</p> <p>32 pits. Archeological features may be</p> <p>33 managed as tall and less frequently</p> <p>34 mown (<12 inches in height) to</p> <p>35 further differentiate.</p> <p>36</p> <p>37 ° Plant the reconstructed mounds with</p> <p>38 a low mown vegetation (<6 to 12</p> <p>39 inches in height).</p> <p>40</p> <p>41 ° Plant the reconstructed earthen wall</p> <p>42 with a low mown vegetation (<6 in</p> <p>43 height).</p> <p>44</p> | <p>1 ° Plant the reconstructed borrow pits</p> <p>2 (7) with low mown vegetation (<6 in</p> <p>3 height).</p> <p>4</p> <p>5 ° Plant the spaces within the earthen</p> <p>6 walls with a low mown vegetation (3</p> <p>7 to <6 in height).</p> <p>8</p> <p>9 ° Plant the non-extant mounds (24, 25</p> <p>10 X1, X2) with a taller mown vegetation</p> <p>11 (<12 inches) prior to rehabilitation.</p> <p>12</p> <p>13 ° Plant the northeast borrow pit with</p> <p>14 a shorter mown vegetation to assist</p> <p>15 with visibility.</p> <p>16</p> <p>17 3. Maintain the North Forty as a mix of</p> <p>18 native herbaceous species, mown 1 to</p> <p>19 2 times per year. Allow for mowing to</p> <p>20 accommodate planned archeological</p> <p>21 research.</p> <p>22</p> <p>23 4. Maintain riparian vegetation along</p> <p>24 the river edge, and existing woodland</p> <p>25 vegetation around the earthwork</p> <p>26 complex.</p> <p>27</p> <p>28 ° Remove exotic, invasive species as</p> <p>29 possible in the woodlands, using an</p> <p>30 integrated pest management plan.</p> <p>31</p> <p>32 5. Establish wooded edges at key locations</p> <p>33 and at the property boundaries to screen</p> <p>34 adjacent development.</p> <p>35</p> <p>36 a. Add a screen of trees between the</p> <p>37 visitor center and the earthwork</p> <p>38 complex, prior to removal of visitor</p> <p>39 center.</p> <p>40</p> <p>41 b. Add a screen of trees and shrubs at</p> <p>42 the southern property boundary,</p> <p>43 to create a buffer between the</p> <p>44 archeological landscape and adjacent</p> <p>45 use to the south. Work with adjacent</p> <p>46 land owners to establish and maintain</p> <p>47 the screen.</p> |
|--|--|
-
- 6-29 Stubbendiek, *Review of the Literature on the Influence of*
Roots.

- c. Work with Ross Correctional Institute to provide a screen of trees and shrubs as a visual buffer on the west side of SR 104.

Buildings and Structures

Mound City Group will continue as a primary visitor orientation facility, however all buildings and structures will be relocated as far from the earthwork complex as possible, in order to protect the setting of the archeological landscape.

1. Evaluate buildings and structures that may be significant in their own right, but that are non-contributing features to the archeological landscape. This includes the Mission 66 Visitor Center and the administration building.
2. Relocate the visitor center, administrative and maintenance facilities off-site or in a location that is less intrusive to the earthwork complex, to be determined.
 - a. Remove existing picnic area, including picnic shelter, tables, and corresponding small scale features. Remove the wood framed shelter at the canal lock stones.
 - b. Locate any new buildings or structures off-site or a less intrusive location on-site. ⁶⁻³⁰

Small Scale Features


The small scale features at Mound City Group will play a minor role and will not detract from the archeological landscape. Any new small scale features will be minimal and unobtrusive.

⁶⁻³⁰ Per the GMP, "Facilities will be designed, located, and managed to minimize impacts on resources and to maximize the quality of the visitor experience. ... Only the development necessary to properly guide visitors and protect resources will be allowed... and will be out of site of the earthworks" (GMP, 18-19).

1. Further investigation is needed into the significance of some small scale features. Evaluate features that may be significant in their own right, but that are non-contributing features to the archeological landscape, including the CCC/WPA walls and steps.

- a. Remove small scale features that are found to be non-contributing and do not serve an active role in interpretation of the earthwork complex.
2. Maintain small scale features that serve an active role in visitor interpretation or experience of the earthwork complex.
 - a. Maintain the WPA/CCC walls at the entrance, and repair as needed.
 - b. Maintain the WPA/CCC walls along the river trail, and repair as needed.
 - c. Maintain and repair the WPA/CCC stone grill.
 - d. Preserve the canal lock stones remaining from the Ohio Erie Canal. While these are not contributing features, these stones are part of the overall history of the area and will be preserved in-situ.


3. Design and situate new small scale features such as signs and interpretive panels, to be low-profile and unobtrusive within sight of the earthwork complex.



- Legend**
- NPS Boundary
 - 100 Year Floodplain
 - River Embankment
 - Woodland
 - Tall Grass and Forbs
 - Low Mixed Grasses
 - Trail
 - Existing Mound / Wall to Protect
 - Borrow Pit - Mark with Vegetation
 - Non Extant Feature - Rehabilitate
 - Existing Large Mound - Potential Rehabilitate with Cobble Marking

Sources:
FEMA Floodplains Map #39141C0200D, 39141C0355D, 39141C0335D, 39141C0175D; <http://www.fws.gov/wetlands/Data/Mapper.html>; 2014 Google Maps; 1978 Mound City Land Use Plan

TIC# 353 128149



| | | | |
|---|---|----------------|--------------------|
| MARCH 2016 | TITLE OF PROJECT CULTURAL LANDSCAPE REPORT AND ENVIRONMENTAL ASSESSMENT | | |
| UNITED STATES DEPARTMENT OF THE INTERIOR HOPEWELL CULTURE NATIONAL HISTORICAL PARK | TITLE OF DRAWING MOUND CITY GROUP - PREFERRED ALTERNATIVE | | |
| ILLUSTRATION 6-3 | NAME OF PARK HOPEWELL CULTURE NATIONAL HISTORICAL PARK | | |
| | REGION MIDWEST | COUNTY ROSS | STATE OHIO 6-29 |

Hopeton Earthworks

1 The treatment plan for Hopeton Earthworks
 2 emphasizes research and education. The
 3 majority of the site will not be open to the
 4 general public. Limited development will
 5 allow visitors to learn about the Hopewell
 6 culture from a distance and to view the
 7 earthworks.⁶⁻³¹ The archeological landscape
 8 will be protected and marked to focus
 9 visitor experience on the creation and
 10 use of the earthwork complex. This will
 11 be accomplished through preservation of
 12 extant below- and above-grade archeological
 13 features. Because Hopeton Earthworks is
 14 located within the 100-year flood zone, this
 15 includes protection of the riparian corridor
 16 vegetation and avoiding treatments that
 17 would have potential to increase flooding
 18 risks. In addition, the legibility and visibility
 19 of the earthwork complex will be increased
 20 by better delineation of the archeological
 21 features. Visitor experience will be improved
 22 by management of circulation, vegetation, and
 23 views. In addition, non-contributing features
 24 will be removed.

25

26 Preservation is the treatment approach for
 27 Hopeton Earthworks. This approach protects
 28 and preserves those features which convey its
 29 historic and cultural significance.

30

31 Treatment goals for Hopeton Earthworks
 32 include the following:

33

- 34 • Preserve extant above-grade archeological
 35 features.
- 36
- 37 • Spatially depict the three-dimensional
 38 earthwork complex.
- 39
- 40 • Provide opportunities for visitors to
 41 access and view the earthwork complex.
- 42
- 43 • Reveal the relationship to the river and
 44 Mound City Group.

- 1 • Remove non-contributing features that
 2 impact visitor's ability to discern the
 3 archeological landscape.
- 4

- 5 • Provide an authentic visitor experience.
- 6

7 The treatment plan for Hopeton Earthworks
 8 (ILLUSTRATION 6-4) illustrates the desired
 9 landscape condition.

11 Spatial Organization/Topography/Views

12 The vision for the spatial organization is for
 13 the forms and patterns of the archeological
 14 landscape to be revealed. The spatial qualities
 15 of the earthwork complex will be depicted to
 16 improve visitor's understanding.

- 17
- 18 1. The spatial organization will be repaired
 19 through removal of non-contributing
 20 features; removal of vegetation that
 21 obscures the earthwork complex and
 22 archeological features; protection and
 23 marking of non-extant above-grade
 24 archeological features; and establishing
 25 pedestrian circulation routes to provide
 26 views of the earthwork complex.
- 27
- 28 a. Spatially depict the three-dimensional
 29 form of the earthwork complex and
 30 surroundings using vegetation or
 31 by marking nonvisible archeological
 32 features.
- 33
- 34 b. Remove hazardous trees and woody
 35 vegetation that impact the earthwork
 36 complex or diminish the visitor's
 37 understanding of the earthwork's
 38 spatial qualities. In particular, remove
 39 vegetation impacting Circle A and
 40 fencerow vegetation north and west
 41 of the Great Circle.
- 42
- 43 c. Delineate the mass, scale and form
 44 of the earthwork complex by using
 45 vegetation to mark non-extant above-

6-31 GMP, 34

grade archeological features, i.e.,
earthen walls, mounds, and borrow
pits, and the spaces of the earthwork.

d. Work with property owners to
establish protection (through
acquisition, easements or other
agreements) for the land within the
bend of the Scioto River surrounding
the Hopeton Earthworks to
manage for conservation and visual
consistency with the earthwork
complex.

e. Create a view between the earthwork
complex and the river, and between
the Mound City Group and Hopeton
Earthworks, by thinning vegetation
along a portion of the riverbank.

f. Provide interpretive information
about the earthwork complex and
cosmology.

g. Consider using alternative media
to provide visitors with access
to large amounts of research and
documentation of features at the park
unit—keyed to specific locations – to
enhance visitors understanding of
the authenticity of the earthwork
complex.

Archeological Features

The treatment plan provides for protection
and marking of archeological features. All
extant below- and above- grade archeological
features, as well as spaces with known
or potential archeological scatter will be
preserved, stabilized and repaired as needed,
following best practices. The archeological
features will be marked with vegetation and
interpreted to provide a compelling visitor
experience. Non-extant archeological features
will be marked with vegetation to depict their
mass, form, and character, as documented by

Squire and Davis in 1846, or based upon most
recent archeological investigations. Refer to
the cross section examples provided under
Study Area for a graphic representation of
applicable techniques (ILLUSTRATION 6-1).

1. Investigations and Research. Continue
investigations and archeological research,
including the following research needs.

a. Identify currently unknown
resources at the outlying areas using
magnetometry or other non-invasive
archeological techniques.

b. Investigate techniques for marking
of archeological features to fully
understand potential impacts on
below-grade archeological features.

2. Best Practices - Preservation of Features.
Preserve all extant below- and above-
grade archeological features. Stabilize and
repair features as necessary, following
best practices.

a. Preserve all extant below- and above-
grade archeological features.

b. Stabilize and repair archeological
features as needed, following best
practices.

c. Do not allow visitor access on top of
the mounds or earthen walls or in
borrow pits.

d. Monitor the streambank and stabilize
areas of erosion that threaten
archeological resources.

3. Repair of Archeological Spaces. Repair archeological spaces to reveal their mass, form, and scale. Delineate the earthwork complex by marking archeological features when no discernible topographical relief occurs in LiDAR imagery or through visual observations.

a. Depict the archeological space of the earthwork complex through the following techniques. Use a consistent palette of materials.

- ° Use one consistent vegetation type and vegetation management technique to depict the space of the enclosure and earthwork complex.
- ° Use a different vegetation management technique for archeological features such as mounds and earthen walls to differentiate between the three-dimensional archeological features and adjacent spaces.
- ° Use a taller grass / herbaceous mix at the edges of the archeological spaces and in areas of archeological scatter, to distinguish these from the surrounding landscape.

4. Marking of Archeological Features. Marking of non-extant archeological features using vegetation is recommended.

- ° Cross section examples provided in ILLUSTRATION 6-1 represent examples of applicable rehabilitation techniques.
- b. Use vegetation to depict outlines and dimensions of verified non-extant archeological and other above-grade features.

° Verified features to be delineated include the following.

- Portions of the Great Circle walls
- Portions of the Square Enclosure walls
- Portions of the Parallel Walls
- Circle B
- Circle C
- Three mounds within the Square Enclosure
- Borrow pits

° Specific features to be delineated when verified include the following.

- Circle A
- Unverified portions of the Parallel Walls.

Circulation

The vision for the circulation system at Hopeton Earthworks is to establish visitor access and interpretive routes to provide visitors with an understanding of the physical earthwork complex. An entrance road, parking area, and pedestrian routes will be added. Pedestrian trails, an overlook and wayside will be established to provide access.

Access to the earthwork complex via the river will be improved to reflect this circulation route that existed at the time of the Hopewell. A new trail and bridge will be added, establishing a link to Mound City Group.

1. Vehicular Circulation. The existing vehicular circulation system at Hopeton Earthworks will be modified to provide access for visitors and to remove routes that impact the archeological landscape.

- a. Remove vehicular circulation routes that do not contribute to the significance of the archeological landscape and impact the integrity

of the known extant archeological features.

- ° Remove the quarry access road that runs over the Square Enclosure.

- ° Remove Pit Road, Overly Road, quarry service routes, and Vaughn Road.

- b. Provide a parking area on the north side of Hopetown Road.

2. Pedestrian Circulation. Add pedestrian trails, an overlook, and an interpretive wayside.

- a. Establish trails that allow for understanding of the earthworks.

- b. Near the parking lot, construct an embankment and install a drainage pipe to allow drainage to/from Dry Run.

- c. Provide an overlook east of Circles B and C to present a visual overview of the earthwork complex.

- d. Create pedestrian routes between Hopeton Earthworks and Mound City Group.

- ° Provide a trail along Hopetown Road to Mound City Group.

- ° Build a pedestrian bridge across the Scioto River to connect to Mound City Group.

- e. Provide access to the river bank at Mound City Group by creating a new kayak / canoe access.

- f. Create an interconnected water route between all park units with new canoe / kayak access.

1 Vegetation

2 Treatment of vegetation at Hopeton

3 Earthworks will focus on creating
4 greater visibility and preservation of the
5 archeological features. Vegetation will be
6 managed to assist in defining the spatial
7 organization of the earthwork complex,
8 framing views and screening undesirable
9 views.

10
11 The earthwork complex will be maintained
12 free of woody vegetation surrounded by
13 grassland. This appearance will be achieved
14 by removing trees and fencerow vegetation
15 and reintroducing grasses. Woodland will
16 be retained along the eastern and southern
17 property lines.

18
19 1. Vegetation types and management
20 techniques will be used to preserve the
21 archeological features.

- 22
23 a. Remove trees and woody vegetation
24 that impact archeological features
25 or diminish the spatial qualities of
26 the earthwork complex. However,
27 if vegetation is helping to stabilize
28 archeological features, do not remove
29 it.

- 30
31 ° Remove woody vegetation on Circle A.

- 32
33 ° Remove fencerow vegetation between
34 the Great Circle and Circle A.

- 35
36 ° Add vegetation north of Circle A to
37 screen adjacent land use.

- 38
39 ° Remove fencerow vegetation north
40 and west of the Great Circle.

- 41
42 ° Allow for shade trees, provided they
43 do not negatively impact archeological
44 resources.

- 45
46 b. Reintroduce grasses where trees and
woody vegetation have been removed.

-
- | | | | | |
|----|----|--|----|--|
| 1 | 2. | Utilize distinct vegetation types to reveal | 1 | remove the buildings and structures that |
| 2 | | the form and spaces of the earthwork | 2 | are impacting the earthwork complex |
| 3 | | complex: | 3 | including: the quarry operation buildings, |
| 4 | | | 4 | structures, roads, and utilities. |
| 5 | a. | Use a low growing grass mix (<6 | 5 | |
| 6 | | to 12 inches in height) in spaces of | 6 | |
| 7 | | the earthwork complex including | 7 | |
| 8 | | the enclosure, mounds and borrow | 8 | |
| 9 | | pits. Archeological features may be | 9 | |
| 10 | | managed as tall and less frequently | 10 | |
| 11 | | mown to further differentiate. | 11 | |
| 12 | | | 12 | |
| 13 | b. | Use tall grasses and forbs in areas | 13 | |
| 14 | | surrounding the earthwork complex. | 14 | |
| 15 | | | 15 | |
| 16 | 3. | Maintain vegetation that stabilizes steep | 16 | |
| 17 | | slopes or protects archeological features | 17 | |
| 18 | | from impacts. | 18 | |
| 19 | | | 19 | |
| 20 | a. | Vegetation along the streambanks of | 20 | |
| 21 | | Dry Run. | 21 | |
| 22 | | | 22 | |
| 23 | b. | Vegetation that screens views to | 23 | |
| 24 | | the south and east of the earthwork | 24 | |
| 25 | | complex. | 25 | |
| 26 | | | 26 | |
| 27 | 4. | Add vegetation on the north of Circle | 27 | |
| 28 | | A, to screen views from the complex to | 28 | |
| 29 | | adjacent land use. | 29 | |
| 30 | | | 30 | |
| 31 | | Buildings and Structures | 31 | |
| 32 | | Long-term treatment recommendations are | 32 | |
| 33 | | to remove all buildings and structures from | 33 | |
| 34 | | the earthwork complex and surrounding | 34 | |
| 35 | | area, in order to protect the setting of the | 35 | |
| 36 | | archeological landscape. | 36 | |
| 37 | | | 37 | |
| 38 | 1. | Remove buildings and structures that do | 38 | |
| 39 | | not contribute to the significance of the | 39 | |
| 40 | | archeological landscape and impact the | 40 | |
| 41 | | integrity of the known extant earthwork | 41 | |
| 42 | | complex including the utility lines and | 42 | |
| 43 | | poles adjacent to the quarry access road | 43 | |
| 44 | | that crosses over the Square Enclosure. | 44 | |
| 45 | | | 45 | |
| 46 | 2. | NPS will work with property owners to | 46 | |
| 47 | | develop a long-term plan to eventually | | |

Page left intentionally blank.



Legend

- Legislated Boundary
- Protect Adjacent Lands
- 100 Year Floodplain
- Creek Embankment
- Woodland
- Tall Grass and Forbs
- Low Mixed Vegetation
- Trail
- P Parking
- Existing Feature to Protect and Mark with Vegetation
- Earthen Wall / Feature to Protect and Mark with Vegetation
- Unverified Feature to Protect and Mark with Vegetation
- Historic Borrow Pit to Protect and Mark with Vegetation
- Borrow Pit to Protect and Mark with Vegetation
- O Overlook
- W Wayside

Note:

Since site documentation was completed in October 2014, the parking lot at Hopetown Road and trail between the parking lot and overlook have been designed through a separate project. Therefore, these features are treated as existing conditions in the preferred alternative for the CLR/EA.

*Locations for mown trails may vary.

TIC# 353 128149

| | |
|--|---|
| MARCH 2016 | TITLE OF PROJECT CULTURAL LANDSCAPE REPORT AND ENVIRONMENTAL ASSESSMENT |
| UNITED STATES DEPARTMENT OF THE INTERIOR | TITLE OF DRAWING HOPEWELL EARTHWORKS - TREATMENT PLAN |
| HOPEWELL CULTURE NATIONAL HISTORICAL PARK | NAME OF PARK HOPEWELL CULTURE NATIONAL HISTORICAL PARK |
| ILLUSTRATION 6-4 | REGION MIDWEST |
| | COUNTY ROSS |
| | STATE OHIO |
| | 6-37 |

Hopewell Mound Group

1 In accordance with the GMP, visitor use
 2 and interpretation will be emphasized at
 3 the Hopewell Mound Group. Legislated
 4 boundaries will be expanded to ensure
 5 maximum protection of archaeological
 6 resources and the landscape context of the
 7 earthworks, including the viewshed.⁶⁻³² The
 8 treatment plan for Hopewell Mound Group
 9 emphasizes the interpretation of Hopewell
 10 Culture. The archeological landscape will
 11 be rehabilitated to focus visitor experience
 12 on the creation and use of the earthwork
 13 complex. This will be accomplished through
 14 preservation of extant below- and above-
 15 grade archeological features. Also, the
 16 legibility and visibility of the earthwork
 17 complex will be improved by delineating
 18 the archeological features and the visitor
 19 experience will be enhanced by managing
 20 circulation, vegetation, and views.
 21
 22 Rehabilitation is the treatment approach for
 23 the Hopewell Mound Group. Rehabilitation
 24 allows for compatible use through repair,
 25 alterations, and additions while preserving
 26 those features that convey historic and
 27 cultural significance.
 28
 29 Treatment goals for Hopewell Mound Group
 30 include the following:
 31
 32 • Preserve extant above-grade archeological
 33 features.
 34
 35 • Spatially depict the three-dimensional
 36 earthwork complex.
 37
 38 • Reveal the relationship to the river and
 39 other earthwork complexes.
 40
 41 • Remove non-contributing features that
 42 impact visitor's ability to discern the
 43 archeological landscape.
 44
 45 • Provide an authentic visitor experience.

1 The treatment plan for Hopewell Mound
 2 Group (ILLUSTRATION 6-5) illustrates the
 3 desired landscape condition.
 4

5 Spatial Organization/Topography/Views

6 The vision for the spatial organization is
 7 for forms and patterns of the archeological
 8 landscape to be revealed. The full spatial
 9 qualities of the earthwork complex and the
 10 relationship to the surrounding landscape
 11 will be depicted.
 12

- 13 1. Spatial organization will be rehabilitated
 14 through removal of non-contributing
 15 features, removal of vegetation that
 16 obscures the earthwork complex and
 17 archeological features, marking of
 18 non-extant above-grade archeological
 19 features, and establishment of pedestrian
 20 circulation routes that allow for
 21 understanding of the earthworks.
 22
 23 a. Spatially depict the three-dimensional
 24 form of the earthwork complex and
 25 surroundings using vegetation or
 26 by marking nonvisible archeological
 27 features.
 28
 29 b. Remove hazardous trees and woody
 30 vegetation that impact the earthwork
 31 complex and diminish the visitor's
 32 understanding of the spatial qualities
 33 of the earthwork complex.
 34
 35 ° Selectively remove woody vegetation
 36 along the eastern portion of the north
 37 wall of the Great Enclosure to improve
 38 views of the earthwork.
 39
 40 c. NPS will work with the local
 41 community and landowners to
 42 develop a long-term plan for removal
 43 of non-contributing features that
 44 impact spatial organization of the

6-32 GMP, 32

- | | | | |
|----|--|----|--|
| 1 | earthwork complex, including Sulphur | 1 | a. Identify currently unknown |
| 2 | Lick Road and buildings located on | 2 | resources at the outlying areas using |
| 3 | archeological features. | 3 | magnetometry or other non-invasive |
| 4 | | 4 | archeological techniques. |
| 5 | d. Delineate the mass, scale, and form of | 5 | |
| 6 | the earthwork complex by marking | 6 | b. Investigate techniques for marking |
| 7 | non-extant above-grade archeological | 7 | or rehabilitation of archeological |
| 8 | features, i.e., earthen walls, mounds, | 8 | features to fully understand potential |
| 9 | and borrow pits, and the spaces of the | 9 | impacts on below-grade archeological |
| 10 | earthwork. | 10 | features. |
| 11 | | 11 | |
| 12 | e. Provide interpretive information | 12 | 2. <u>Best Practices - Preservation of Features.</u> |
| 13 | about the earthwork complex and | 13 | Preserve all extant below- and above- |
| 14 | cosmology. | 14 | grade archeological features. Stabilize and |
| 15 | | 15 | repair features as necessary, following |
| 16 | f. Consider using alternative media | 16 | best practices. |
| 17 | to provide visitors with access | 17 | |
| 18 | to large amounts of research and | 18 | a. Preserve all extant below- and above- |
| 19 | documentation of features at the park | 19 | grade archeological features. |
| 20 | unit—keyed to specific locations – to | 20 | |
| 21 | enhance visitors understanding of | 21 | b. Stabilize and repair archeological |
| 22 | the authenticity of the earthwork | 22 | features as needed, following best |
| 23 | complex. | 23 | practices. |
| 24 | | 24 | |
| 25 | Archeological Features | 25 | c. Do not allow visitor access on top of |
| 26 | The treatment plan provides for protection | 26 | the mounds or earthen walls or in |
| 27 | and rehabilitation of archeological features. | 27 | borrow pits. |
| 28 | All extant below- and above- grade | 28 | |
| 29 | archeological features, as well as spaces with | 29 | d. Monitor the streambank and stabilize |
| 30 | known or potential archeological scatter | 30 | areas of erosion that threaten |
| 31 | will be preserved, stabilized and repaired | 31 | archeological resources. |
| 32 | as needed, following best practices. The | 32 | |
| 33 | archeological features will be marked and | 33 | 3. <u>Rehabilitation of Archeological</u> |
| 34 | interpreted to provide a compelling visitor | 34 | <u>Spaces.</u> Rehabilitate archeological |
| 35 | experience. Non-extant archeological features | 35 | spaces to reveal their mass, form and |
| 36 | will be marked to depict their mass, form | 36 | scale. Delineate the earthwork complex |
| 37 | and character, as documented by Shetrone | 37 | by marking archeological features when |
| 38 | in 1922 to 1925, or based upon most recent | 38 | no discernible topographical relief occurs |
| 39 | archeological investigations. Refer to the cross | 39 | in LiDAR imagery or through visual |
| 40 | section examples provided under Study Area | 40 | observations. |
| 41 | for a graphic representation of applicable | 41 | |
| 42 | rehabilitation techniques (ILLUSTRATION | 42 | a. Depict the archeological space of |
| 43 | 6-1). | 43 | the earthwork complex through the |
| 44 | | 44 | following techniques. Use a consistent |
| 45 | 1. <u>Investigations and Research.</u> Continue | 45 | palette of materials. |
| 46 | investigations and archeological research, | 46 | |
| 47 | including the following research needs. | | |

| | | | |
|----|---|----|---|
| 1 | ° Use one consistent vegetation | 1 | verified non-extant archeological and |
| 2 | type and vegetation management | 2 | other above-grade features. |
| 3 | technique to depict the space of the | 3 | |
| 4 | enclosure and earthwork complex. | 4 | ° Use a non-permanent material that |
| 5 | | 5 | differs from the extant materials |
| 6 | ° Use a different vegetation | 6 | of the archeological features to |
| 7 | management technique for | 7 | differentiate these as contemporary |
| 8 | archeological features such as mounds | 8 | features. |
| 9 | and walls to differentiate between | 9 | |
| 10 | the three-dimensional archeological | 10 | ° Verified features to be delineated |
| 11 | features and adjacent spaces. | 11 | include the following. |
| 12 | | 12 | |
| 13 | ° Use a taller grass / herbaceous mix | 13 | – Southern portion of the east wall of |
| 14 | at the edges of the archeological | 14 | the Great Enclosure. |
| 15 | spaces and in areas of archeological | 15 | – South, east and north walls of the |
| 16 | scatter; to distinguish these from the | 16 | Square Enclosure. |
| 17 | surrounding landscape. | 17 | – East and south walls of the D-Shaped |
| 18 | | 18 | Enclosure. |
| 19 | ° Maintain a distinct vegetation | 19 | – North, east, and south walls of the |
| 20 | management technique to | 20 | Great Circle. |
| 21 | differentiate between the | 21 | – Five mounds. |
| 22 | earthwork complex and visitor and | 22 | |
| 23 | administrative / maintenance areas. | 23 | ° Specific features to be delineated |
| 24 | | 24 | when verified include the following. |
| 25 | 4. <u>Rehabilitation of Archeological Features.</u> | 25 | |
| 26 | Rehabilitation of non-extant archeological | 26 | – North portion of west wall of the |
| 27 | features is recommended. This may | 27 | Great Enclosure. |
| 28 | include creating three-dimensional | 28 | – South portion of the west wall of the |
| 29 | depictions using new soil or the use of | 29 | Great Enclosure. |
| 30 | vegetation. | 30 | – Portions of the north and west walls |
| 31 | | 31 | of the D-Shaped Enclosure. |
| 32 | a. Rehabilitate non-extant archeological | 32 | – Portion of the west wall of the Great |
| 33 | features to depict their mass, form, | 33 | Circle. |
| 34 | and character, as documented by | 34 | – Thirty-three mounds. |
| 35 | Shetrone in 1922 to 1925, or based | 35 | – The ditch at the southeast portion of |
| 36 | upon most recent archeological | 36 | the east wall of the Great Enclosure. |
| 37 | investigations. | 37 | – The ditch around the Great Circle. |
| 38 | | 38 | – The ditch around the D-Shaped |
| 39 | ° Cross section examples provided | 39 | Enclosure. |
| 40 | in ILLUSTRATION 6-1 represent | 40 | – The ditch at the northern portion of |
| 41 | examples of applicable rehabilitation | 41 | the west wall of the Great Enclosure. |
| 42 | techniques. | 42 | |
| 43 | | 43 | |
| 44 | b. Use markings, e.g. soil, rock cobble, | 44 | |
| 45 | gravel paths, flags, or vegetation to | 45 | |
| 46 | depict outlines and dimensions of | 46 | |

1 Circulation

2 The existing circulation system at Hopewell
3 Mound Group will be modified to remove
4 routes that do not relate to the archeological
5 landscape, and add routes that foster
6 understanding of the archeological landscape.
7 The vision for the circulation system at
8 Hopewell Mound Group is to improve existing
9 pedestrian circulation by adding routes that
10 allow for understanding of the earthwork
11 complex and removing routes that do not
12 support this goal. Sulphur Lick Road and the
13 bicycle route will eventually be removed from
14 locations where they impact the earthwork
15 complex. The visitor parking area will remain
16 in its current location with access provided
17 from the east.

18
19 Access to the earthwork complex via the river
20 will be added to reflect this circulation route
21 that existed at the time of the Hopewell.

22
23 1. Vehicular Circulation. Remove vehicular
24 routes that impact the earthwork
25 complex.

26
27 a. NPS will work with the township
28 and other local community
29 representatives to develop a long-
30 range plan to remove the portions of
31 Sulphur Lick Road and the trail that
32 are impacting the earthwork complex.
33 This will occur only when local access
34 needs have been addressed.

35
36 2. Pedestrian Circulation. Add pedestrian
37 trails and an overlook, update existing
38 overlooks, and add links to the North
39 Fork Paint Creek to improve visitor
40 understanding of the earthwork complex.

41
42 a. Retain the existing overlook and
43 viewshed at the northeast corner of
44 the Great Enclosure and update the
45 wayside.

46

- 1 b. Add a new overlook at a location
2 to the west of the existing overlook
3 that gives the best overview of the
4 earthwork complex.
5
6 c. Update the existing overlook on the
7 east side of the Square Enclosure to
8 provide improved orientation to the
9 earthwork complex.
10
11 d. Create pedestrian and bicycle links to
12 the North Fork Paint Creek to improve
13 the relationship of the earthwork
14 complex to the river.
15
16 e. Relocate the rails to trails path to the
17 south of the south wall of the Great
18 Enclosure.
19
20 f. Create an interconnected water route
21 between all park units with a new
22 canoe / kayak access.

24 Vegetation

25 Treatment of vegetation at Hopewell Mound
26 Group will focus on creating greater visibility
27 and preservation of the archeological
28 features. Vegetation will be managed to
29 assist in defining the spatial organization of
30 the earthwork complex, framing views and
31 screening undesirable views.

32
33 In most locations, the earthwork complex
34 will be maintained free of woody vegetation
35 surrounded by grassland. This appearance
36 will be achieved by removing trees and
37 fencerow vegetation and reintroducing
38 grasses. Woody vegetation will be
39 maintained in locations where it is protecting
40 archeological resources.

41
42 1. Vegetation types and management
43 techniques will be used to preserve the
44 archeological features.

45

46

2. Utilize distinct vegetation types to reveal the form and spaces of the earthwork complex:

a. Use a low growing grass mix (<6 to 12 inches in height) in spaces of the earthwork complex, mounds, and borrow pits. Archeological features may be managed as tall and less frequently mown to further differentiate.

b. Use tall grass and forbs in areas surrounding the earthwork complex.

3. Maintain vegetation that stabilizes steep slopes or protects the earthwork complex from impacts.

a. Maintain vegetation along the west portion of the north wall of the Great Enclosure.

b. Maintain vegetation that screens views to the visitor parking area at the east side of the earthwork complex.

4. Add vegetation to screen undesirable views at the southwest portion of the property.

Buildings and Structures

Long-term treatment recommendations are to remove all buildings and structures from the earthwork complex, in order to protect the setting of the archeological landscape.

1. The park will work with property owners to develop a long-term plan to remove buildings that impact the earthwork complex.

2. The park will work with utility companies to develop a long-term plan to mitigate the effects of the high-voltage transmission towers and overhead

lines that are impacting the earthwork complex. Removal is the preferred option, but other possible choices for mitigation could include:

a. Relocation of transmission towers and lines to a new site beyond the viewshed of the earthwork complex (off NPS property).

b. Relocation of transmission towers and lines to a location where they do not impact the earthwork complex within NPS property.

c. Replace transmission towers with substations outside the earthwork complex and relocate high voltage lines underground.


d. Replace the existing lattice towers with less intrusive towers.

e. Move the existing overlook to minimize the visual impact of the towers by orienting views to the north south rather than east west.

Small Scale Features

The small scale features at Hopewell Mound Group play a minor role and do not distract from the archeological landscape. Any new small scale features will be minimal and unobtrusive.

Page left intentionally blank.



- Legend**
- Legislated Boundary
 - ▨ Protect Adjacent Lands
 - 100 Year Floodplain
 - ▨ Creek Embankment
 - Woodland
 - Tall Grass and Forbs
 - Low Mixed Vegetation
 - Trail
 - V** Visitor Orientation
 - P** Parking
 - Existing Feature to Protect and Mark
 - Earthen Wall / Feature to Mark
 - Unverified Feature - Potential to Mark
 - Existing Ditch / Borrow Pit to Mark with Vegetation
 - Ditch - Potential to Mark
 - O** Overlook
 - Unverified Habitation Site- Potential to Mark with Vegetation

Seip Earthworks

The treatment plan for Seip Earthworks emphasizes the interpretation of Hopewell ceremonialism. The archeological landscape will be rehabilitated to focus visitor experience on the creation and use of earthwork. This will be accomplished through delineation of previously unreconstructed mounds and earthen walls, improvements in circulation routes, removal of damaging vegetation, and separation between the visitor orientation area and the ceremonial landscape. Located within the 100-year flood zone, treatment recommendations for Seip Earthworks include protecting the riparian corridor to maintain a healthy stream corridor, and placing visitor services out of the floodplain. In accordance with the GMP, Seip Earthworks will provide a gateway for a grand tour of the Hopewell sites, with interpretive facilities and linkages with the nearby school and community.⁶⁻³³

Rehabilitation is the treatment approach for Seip Earthworks. Rehabilitation allows for compatible uses through repair, alterations, and additions while preserving those features which convey its historic and cultural significance.

Treatment goals for Seip Earthworks include the following:

- Preserve extant above-grade archeological features.
- Spatially depict the three-dimensional earthwork complex.
- Relocate visitor facilities (buildings, roads, parking, etc.) away from the earthwork complex.
- Reveal the relationship to the river and other earthwork complexes.

⁶⁻³³ GMP, 36.

- Remove non-contributing features that impact the visitor's ability to discern the archeological landscape.

- Provide an authentic visitor experience.

The preferred alternative for Seip Earthworks includes protecting all archeological features either through conservation easements or acquiring property from willing sellers, in order to protect the entirety of the earthwork. Currently, portions of the Large Circle and Small Circle are in private ownership. Agreements with adjacent properties will be necessary to provide visitor access to the parking and orientation area.

The treatment plan for Seip Earthworks (ILLUSTRATION 6-6) illustrates the desired landscape condition.

Spatial Organization/Topography/Views

The vision for the spatial organization is for the forms and patterns of the archeological landscape to be revealed. The full spatial qualities of the earthwork complex and the relationship to the surrounding landscape will be depicted.

1. The spatial organization will be rehabilitated through removal of non-contributing features; removal of vegetation that obscures the earthwork complex and archeological features; rehabilitation of non-extant above-grade archeological features; and establishing pedestrian circulation routes that assist in defining the spatial qualities of the earthwork complex.
 - a. Spatially depict the three-dimensional form of the earthwork complex and surroundings through markings and vegetation.

b. Remove hazardous trees and woody vegetation that impact archeological features or diminish the visitor's understanding of the spatial qualities of the earthwork complex and individual spaces.

° When considering the removal of trees for visitor understanding of spatial qualities, consider benefit of shade trees in some locations, provided they will not damage archeological resources.

c. Remove non-contributing features from the immediate surroundings of the earthwork complex.

° Remove the Blackstone House, and fish camp buildings.

° Relocate the picnic shelter, parking, roads and utilities either to a less intrusive area on-site further from the earthwork complex, or off-site.

d. Maintain a consistent vegetation type on the archeological features to distinguish them from visitor areas and the adjacent landscape.

e. Add a dense screen of trees and vegetation between the earthwork complex and the adjacent properties on the north and east.

f. Create a view between the earthwork complex and the river, by thinning vegetation along a portion of the riverbank.

g. Work with property owners to establish protection (through easements or other agreements) for the inholding on U.S. 50, west third of small circle and buffer around the

east half of the square to manage for conservation and visual consistency with the earthwork complex.

Archeological Features

The treatment plan provides for protection and rehabilitation of the archeological features at Seip Earthworks.

1. Investigations and Research. Continue investigations and archeological research, including the following research needs.

a. Currently, less information is available on the form and height of earthwork complex at Seip Earthworks. New research is helping to fill this gap, however the treatment recommendations favor "softer" approaches to mound and earthwork marking until such time as research informs a "harder" approach to rehabilitation.

b. Identify currently unknown resources at the outlying areas using magnetometry or other non-invasive archeological techniques.

2. Best Practices - Preservation of Features. Preserve all extant below- and above-grade archeological features. Stabilize and repair features as necessary, following best practices.

a. Preserve and maintain the existing reconstructed Seip-Pricer Mound and the reconstructed wall of the Large Circle as contributing features.

b. Stabilize and repair archeological features as needed, following best practices.

c. Do not allow visitor access on top of the mounds, borrow pits, or earthen walls.

- | | |
|---|--|
| <p>1 3. <u>Rehabilitation of Archeological Spaces.</u></p> <p>2 Rehabilitate archeological spaces to reveal</p> <p>3 their mass, form, and scale. Delineate</p> <p>4 the earthwork complex by markings</p> <p>5 or rehabilitating archeological features</p> <p>6 when no discernible topographical relief</p> <p>7 occurs in LiDAR imagery or through</p> <p>8 visual observations. The desired aesthetic</p> <p>9 should include open spaces with</p> <p>10 vegetation at different heights, that assists</p> <p>11 in the visibility of the earthworks.</p> <p>12</p> <p>13 a. Depict the archeological space of</p> <p>14 the earthwork complex through the</p> <p>15 following techniques. Use a consistent</p> <p>16 palette of materials.</p> <p>17</p> <p>18 b. Use vegetation types or vegetation</p> <p>19 management techniques to</p> <p>20 differentiate between different types</p> <p>21 of features and the surroundings.</p> <p>22</p> <p>23 c. Maintain a different vegetation type</p> <p>24 on the earthwork complex from</p> <p>25 adjacent areas of archeological scatter</p> <p>26 and riparian areas.</p> <p>27</p> <p>28 4. <u>Rehabilitation of Archeological Features.</u></p> <p>29 Rehabilitation of non-extant archeological</p> <p>30 features is recommended. This includes</p> <p>31 creating three-dimensional depictions</p> <p>32 using new soil or vegetation.</p> <p>33</p> <p>34 a. Rehabilitate non-extant archeological</p> <p>35 features to depict their mass, form,</p> <p>36 and character, as documented by</p> <p>37 Squier and Davis in 1848, or based</p> <p>38 upon most recent archeological</p> <p>39 investigations.</p> <p>40</p> <p>41 ° Specific treatment for each</p> <p>42 archeological feature is provided in</p> <p>43 ILLUSTRATION 6-6 Cross section</p> <p>44 examples provided in ILLUSTRATION</p> <p>45 6-1 represent examples of applicable</p> <p>46 rehabilitation techniques.</p> | <p>1 b. Use earthen markings to rehabilitate</p> <p>2 outlines and dimensions of non-extant</p> <p>3 earthen walls.</p> <p>4</p> <p>5 ° Specific features to be rehabilitated</p> <p>6 include the following.</p> <p>7</p> <p>8 – Small Circle</p> <p>9 – Large Circle</p> <p>10 – Large Square</p> <p>11</p> <p>12 ° Where discernible topographical</p> <p>13 relief occurs, only vegetation or non-</p> <p>14 permanent markings will be used to</p> <p>15 delineate features.</p> <p>16</p> <p>17 ° Use the most current, reliable</p> <p>18 archeological investigations to locate</p> <p>19 markings or rehabilitations, and to</p> <p>20 determine the size and scale. At this</p> <p>21 time, the most current information is</p> <p>22 2015 magnetic surveys.</p> <p>23</p> <p>24 ° Use a non-permanent material that</p> <p>25 differs from the extant materials of</p> <p>26 the archeological features and the</p> <p>27 reconstructed Seip-Pricer Mound, to</p> <p>28 differentiate these as contemporary.</p> <p>29</p> <p>30 c. Use vegetation to delineate outlines</p> <p>31 and dimensions of borrow pits.</p> <p>32</p> <p>33 d. Use a cobble marking / cover</p> <p>34 to rehabilitate the outlines and</p> <p>35 dimensions of mounds.</p> <p>36</p> <p>37 ° Specific features to be rehabilitated</p> <p>38 with cobble include the following.</p> <p>39</p> <p>40 – Seip-Pricer Mound</p> <p>41 – Seip Conjoined Mound (Note:</p> <p>42 additional earthen marking needed</p> <p>43 to reflect original mound mass)</p> <p>44</p> <p>45</p> <p>46</p> |
|---|--|

1 Circulation

The existing circulation system at Seip Earthworks will be modified in order to protect the archeological features, and to provide an engaging visitor experience. A new parking area and visitor orientation is recommended to be located at the adjacent Paint Valley High School Property, with pedestrian trails connecting the orientation area, earthwork complex, and river.

1. Vehicular Circulation. The vehicular circulation system will be modified to relocate vehicular routes as far from the earthwork complex as possible.

- a. Remove existing parking area and adjacent pedestrian paths.
- b. Remove road and drive to the Blackstone House.
- c. Remove and relocate Dill Road where it crosses and damages archeological features.
- d. Create a new visitor parking area at the Paint Valley High School Property, with vehicular access from Highway 50.

2. Pedestrian Circulation. The existing pedestrian circulation system will be improved by adding routes that assist in defining the spatial qualities of the earthwork complex. Routes will be added that express and allow for understanding of the earthwork's geometry.

- a. Provide pedestrian access from the new visitor orientation area to the earthwork complex.
- b. Allow for informal pedestrian access inside the earthwork complex, providing access to the Small Circle,

Large Circle, and the small square, connecting to the visitor orientation area.

- c. Provide a trail to Paint Creek that forms a loop trail along the creek and connects back to the earthwork. Create an overlook and canoe/kayak access point on the creek.

- ° Provide access and information to the interconnected water route between all park units.

15 Vegetation

Treatment of vegetation at Seip Earthworks will focus on preservation of the archeological features. Vegetation will be managed to assist in defining the spatial organization of the earthwork complex, to clarify the visitor experience.

1. Vegetation management techniques will be used to preserve the archeological features.

- a. Remove trees and woody vegetation that impact archeological features or diminish the spatial qualities of the earthwork complex, specifically the fencerow vegetation around the perimeter of the previously state-owned property, and the removal of trees at the west half of the Small Circle.

2. Vegetation will be used to interpret various spaces including utilizing different grass types and mowing techniques to indicate spaces and distinct archeological features. Utilize distinct vegetation types to reveal the form and spaces of the earthwork complex:

- a. Use low mown vegetation in spaces of earthwork complexes including

the interior of the Large Circle, Small Circle, and small square (archeological features may be managed as low/mown, or tall/unmown to further differentiate).

- Plant the reconstructed Seip-Pricer Mound with taller vegetation (<6 to 12 inches in height), or marked with a stone cobble cover.
- Plant the earthen walls with taller vegetation (<6 to 12 inches in height).
- Plant the extant Seip-Conjoined Mound with taller vegetation (<6 to 12 inches in height), or marked with a stone cobble cover.
- Plant borrow pits with taller mown vegetation (<6 to 12 inches in height).
- Plant interior spaces of the enclosures with shorter mown vegetation (<6 inches in height).

- b. Use a mix of native herbaceous species maintained consistently (mow 1-2 times per year) in areas surrounding earthwork complex.

3. Maintain woodland and riparian vegetation along the edge of Paint Creek and at the property boundaries.

4. Establish a wooded edge to screen negative views and impacts, specifically to the east to screen the Paint Valley High School.

5. Consider planting shade trees that can benefit visitors in summer or provide scenic landscape value. Provide trees in strategic locations where no known features exist around the earthworks.

Buildings and Structures

The preferred alternative includes assessing the historical significance of the existing structures and removal of these buildings because they negatively impact the archeological landscape. New structures will be added to provide visitor functions, sited away from the archeological features.

1. Evaluate buildings and structures that may be significant in their own right, but that are non-contributing features to the archeological landscape.

- Prepare HABS documentation and/or a National Register evaluation for the Blackstone House to document the building prior to demolition.

- Document the fish camp buildings prior to demolition.

2. Remove non-contributing buildings and structures from the archeological landscape, after full documentation.

- a. Remove the Blackstone House and outbuildings.
- b. Remove fish camp buildings and related structures.
- c. Remove existing picnic area, including picnic shelter, portable restroom, tables, and corresponding small scale features.

3. Add new structures and small scale features for visitor orientation to assist in the interpretation of the earthwork complex on the Paint Valley High School property.

1 **Small Scale Features**

2 The preferred alternative allows for small
3 scale features that assist in visitor experience
4 and interpretation of the earthwork complex.

5
6 Small scale features that are non-contributing
7 and do not serve an active role in
8 interpretation of the earthwork complex will
9 be removed.

10

11 a. Remove small scale features at the
12 picnic area, including parking area
13 bollards, picnic tables, drinking
14 fountain, and trash and recycling
15 receptacles.

16

17 b. Remove small scale features at the
18 Blackstone House, including fences
19 and overhead utility lines.

20

21 c. Remove overhead utility lines on Dill
22 Road.

23

24 4. New small scale features will be minimal
25 and unobtrusive.

26

27 a. Design and situate new small scale
28 features such as signs and interpretive
29 panels, to be low-profile and
30 unobtrusive. Consider movable panels
31 that will not impact resources below-
32 grade.

33

34

35

36

37

38

39

40

41


42

43

44


45

46



Legend

- Legislated Boundary
- Protect Adjacent Lands
- 100 Year Floodplain
- Creek Embankment
- Woodland
- Tall Grass and Forbs
- Low Mixed Vegetation
- Trail
- VO Visitor Orientation
- P Parking
- Existing Mound - Potential Rehabilitate with Cobble Marking
- Unverified Mound / Feature - Potential Mark / Rehabilitate
- Earthen Wall / Feature to Mark / Rehabilitate
- Borrow Pit to Mark with Vegetation



Sources:
Magnetic Survey 2015, GIS HOCU 2012 LiDAR; 1848, High Bank Works, Davis and Squire; Seip Marshall NAD83; [https://m-sc.fema.gov/portal/search?Address Query=chillicothe](https://m-sc.fema.gov/portal/search?Address+Query=chillicothe); <http://www.fws.gov/wetlands/Data/Mapper.html>; 2014 Google Maps
TIC# 353 128149

| | | | | |
|---|---|----------------|---------------|------|
| MARCH 2016 | TITLE OF PROJECT CULTURAL LANDSCAPE REPORT AND ENVIRONMENTAL ASSESSMENT | | | |
| UNITED STATES DEPARTMENT OF THE INTERIOR HOPEWELL CULTURE NATIONAL HISTORICAL PARK | TITLE OF DRAWING SEIP EARTHWORKS - PREFERRED ALTERNATIVE | | | |
| ILLUSTRATION 6-6 | NAME OF PARK HOPEWELL CULTURE NATIONAL HISTORICAL PARK | | | |
| | REGION MIDWEST | COUNTY ROSS | STATE OHIO | 6-53 |

High Bank Works

1 The treatment plan for High Bank Works
 2 emphasizes the interpretation of Hopewell
 3 ceremonialism. The archeological landscape
 4 will be preserved, while allowing visitors to
 5 discover the creation and use of the mounds.
 6 This will be accomplished through delineation
 7 of unreconstructed mounds, improvements in
 8 circulation routes, and removal of damaging
 9 vegetation. In accordance with the GMP,
 10 High Bank Works will be used primarily for
 11 research and as an archeological preserve.⁶⁻³⁴
 12
 13 Preservation is the treatment approach for
 14 High Bank Works. This approach protects and
 15 preserves those features which convey its
 16 historic and cultural significance.
 17
 18 Treatment goals for High Bank Works include
 19 the following:
 20
 21 • Preserve extant above-grade archeological
 22 features.
 23
 24 • Spatially depict the two-dimensional
 25 earthwork complex.
 26
 27 • Locate visitor facilities (roads, parking)
 28 away from earthwork complex.
 29
 30 • Reveal the relationship to the river and
 31 other earthwork complexes.
 32
 33 • Remove non-contributing features that
 34 impact the visitor's ability to discern the
 35 archeological landscape.
 36
 37 • Provide an authentic visitor experience.
 38
 39 The preferred alternative for High Bank
 40 Works includes protecting all archeological
 41 features either through conservation
 42 easements, or acquiring property from willing
 43 sellers, in order protect the entirety of the
 44
 45 ⁶⁻³⁴ HOCU GMP, 39.

1 earthwork. Currently, the middle portion
 2 of the earthwork (the Parallel Walls) are
 3 in private ownership. Easements will be
 4 necessary to provide access to the lower
 5 terrace, the Scioto River, and the South
 6 Earthwork.
 7

8 The treatment plan for High Bank Works
 9 (ILLUSTRATION 6-7) illustrates the desired
 10 landscape condition.
 11

12 Spatial Organization/Topography/Views

13 The vision for the spatial organization
 14 at High Bank Works is for the forms and
 15 patterns of the archeological landscape to
 16 be revealed. The full spatial qualities of the
 17 earthwork complex and the relationship to
 18 the surrounding landscape will be depicted.
 19

- 20 1. The spatial organization will be repaired
 21 through removal of non-contributing
 22 features; removal of vegetation that
 23 obscures the earthwork complex and
 24 archeological features; and establishing
 25 pedestrian circulation routes that assist
 26 in defining the spatial qualities of the
 27 earthwork complex.
 28
 29 a. Spatially depict the three-dimensional
 30 form of the earthwork complex and
 31 surroundings through vegetation
 32 management. Delineate the mass,
 33 scale, and form of the earthwork
 34 complex by marking non-extant
 35 above-grade archeological features,
 36 i.e. earthen walls, mounds, and
 37 borrow pits, and the spaces of the
 38 earthwork.
 39
 40 b. Remove hazardous trees and
 41 woody vegetation that impact the
 42 archeological features or diminish the
 43 visitor's understanding of the spatial
 44 qualities of the earthwork complex
 45 and individual spaces.

c. Remove non-contributing features from the immediate surroundings of the earthwork complex, including buildings, structures, roads, utilities, etc.

d. Maintain a consistent vegetation type on the archeological features to distinguish them from the adjacent landscape. Clarify the forms of the earthwork complex by utilizing two distinct vegetation types. One vegetation type will be used on the earthwork complex, and another type will be used in adjacent areas.

e. Create a view between the earthwork complex and the river, by thinning vegetation along a portion of the riverbank and opening select views of Paint Creek and Scioto River.

f. Add vegetative buffers to screen negative views, specifically the railroad tracks and road at the northeast property line.

Archeological Features

The treatment plan provides for protection and repair of the archeological features at High Bank Works to spatially depict the massive earthen walls, borrow pits, and mounds that are not currently visible. The desired aesthetic should include open spaces and low vegetation that assists with visibility of the earthworks.

1. Investigations and Research. Continue investigations and archeological research, including the following research needs.

a. Identify currently unknown resources at the outlying areas using magnetometry or other non-invasive archeological techniques.

2. Best Practices - Preservation of Features.

Preserve all extant below- and above-grade archeological features. Stabilize and repair features as necessary, following best practices.

3. Repair of Archeological Spaces.

Repair archeological spaces to reveal their form and scale. Delineate the earthwork complex by marking with vegetation or utilizing vegetation management techniques that highlight the archeological features when no discernible topographical relief occurs in LiDAR imagery or through visual observations.

a. Depict the three-dimensional form of the earthwork complex through the use of one or more of the following techniques. Use a consistent palette of materials.

° Use vegetation types or vegetation management techniques to differentiate between the earthwork complex and the surrounding landscape.

° Use a taller grass / herbaceous mix at the edges of the archeological spaces and in areas of archeological scatter, to distinguish these from the earthwork complex and woodland areas.

4. Preservation of Archeological Features.

Non-extant archeological features at High Bank Works will be preserved, and marked through the use of vegetation or other impermanent methods.

a. Repair non-extant archeological features to depict their mass, form and character, as documented by the 2013 Burks magnetic survey, or

based upon most recent archeological investigations.

- ° Specific treatment for each archeological feature is provided in ILLUSTRATION 6-7. Cross section examples provided in ILLUSTRATION 6-1 represent examples of applicable marking techniques.

- b. Use vegetation maintained at different heights to depict outlines and dimensions of non-extant mounds and earthen walls.

- ° Specific features to be delineated include the following.

- Great Circle
- Octagon
- Parallel Walls
- South Earthwork
- Borrow pits

Circulation

The vision for the circulation system at High Bank Works is to remove all non-contributing features, including roads and parking areas, and to add pedestrian routes that assist in defining the spatial qualities of the earthwork complex. Access to the earthwork complex via the river will be added to reflect the circulation route that existed at the time of the Hopewell.

1. Vehicular Circulation. The vehicular circulation system will be modified to remove vehicular routes from the earthwork complex, while providing for safe visitor and maintenance access.
 - a. Remove existing gravel and dirt roads.
 - b. Add a second vehicular route and parking area, open to visitors, at the South Earthwork.

2. Pedestrian Circulation. A network of pedestrian paths will provide access to the earthwork and the edge of the Scioto River.

- a. Improve pedestrian access at the north parking area into the earthwork complex. Work long-term with the railroad company to provide safe access across the railroad tracks.

- b. Improve existing pedestrian circulation by adding routes that allow for understanding of the earthwork complex.

- ° Maintain informal pedestrian circulation routes throughout the interior space of the earthworks.

- ° Add a path from the south vehicular entry into the South Earthwork.

- c. Create a path from the south vehicular entry to the Scioto River. Create a canoe / kayak access at the river edge. Provide a river overlook in this location.

Vegetation

Vegetation at High Bank Works will be managed to provide visibility and preservation of the earthwork complex. Trees and shrubs that grow on the earthwork complex will be removed, hardwood forest will be maintained around the earthwork complex, and riparian vegetation will remain along the river edge.

1. Vegetation management techniques will be used to preserve the archeological features.

- a. Remove hazardous trees and woody vegetation that impact contributing archeological features or diminish

the spatial qualities of the earthwork complex, specifically the area southwest of the Octagon.

- b. Remove the native grassland at the Octagon.

2. Vegetation will be used to interpret various spaces including utilizing different grass types and mowing techniques to indicate spaces and distinct archeological features. Use two distinct vegetation types to reveal the form and spaces of the earthwork complex:

- a. Low/mown vegetation in spaces of earthwork complex including the interior of the Great Circle, Octagon, Parallel Walls and South Earthwork (archeological features may be managed as low/mown, or tall/unmown to further differentiate).

- ° Plant the Great Circle, Octagon, Parallel Walls, and South Earthwork with taller vegetation (<6 inches in height).

- ° Plant borrow pits with taller mown vegetation (<6 inches in height).

- ° Plant interior spaces of the enclosures with shorter mown vegetation (3 to <6 inches in height).

- b. Use a mix of native herbaceous species maintained consistently in areas surrounding earthwork complex.

- ° This could be the same mix as currently used in the Octagon. Mow once a year, in the winter.

3. Maintain woodland and riparian vegetation along the edge of the Scioto River.

- 4. Add a vegetative buffer along the northeast property line to screen the existing railroad and road from the earthwork complex.

Small Scale Features

The preferred alternative allows for small scale features that assist in visitor experience and interpretation of the earthwork complex.


- 1. Small scale features that are non-contributing and do not serve an active role in interpretation of the earthwork complex will be removed.

- a. Remove all non-contributing small scale features. This includes the fence adjacent the Large Circle, the utility poles and lines along the dirt access road.

- 2. Any new small scale features will be minimal and unobtrusive.

- a. Design and situate new small scale features such as signs and interpretive panels, to be low-profile and unobtrusive.


- b. Add a fence along the northeast property line to provide a separation between the earthwork and existing railroad.



- Legend**
- Legislated Boundary
 - ▨ Protect Adjacent Lands
 - 100 Year Floodplain
 - ▨ Creek Embankment
 - Woodland
 - Tall Grass and Forbs
 - Low Mixed Vegetation
 - Trail
 - P Parking
 - Existing Feature to Protect and Mark with Vegetation
 - Unverified Feature to Protect and Mark with Vegetation
 - Earthen Wall / Feature to Protect and Mark with Vegetation
 - Borrow Pit to Protect and Mark with Vegetation

Sources:
Burks 2013 High Bank Works Magnetic Survey; Burks 2013 Turpen Tract-High Bank Works Magnetic Survey; GIS HOCU 2012 LiDAR; 1848, High Bank Works, Davis and Squire; <http://www.fws.gov/wetlands/Data/Mapper.html>; <https://m-sc.fema.gov/portal/>; 2014 Google Maps

TIC# 353 128149



| | | | |
|--|--|---|----------------|
| MARCH 2016 | | TITLE OF PROJECT CULTURAL LANDSCAPE REPORT AND ENVIRONMENTAL ASSESSMENT | |
| UNITED STATES DEPARTMENT OF THE INTERIOR | | TITLE OF DRAWING HIGH BANK WORKS - PREFERRED ALTERNATIVE | |
| HOPEWELL CULTURE NATIONAL HISTORICAL PARK | | NAME OF PARK HOPEWELL CULTURE NATIONAL HISTORICAL PARK | |
| ILLUSTRATION 6-7 | | REGION MIDWEST | COUNTY ROSS |
| | | STATE OHIO | 6-59 |

Implementation

This section provides guidance for implementing the treatment recommendations. The recommendations are organized into distinct tasks, with subtasks identified. These tasks will guide preparation of Project Management Information System (PMIS) project statements.

The tasks are presented by park unit, in table form. Each task has been assigned a phase, or priority, that indicates when implementation should occur. These phases include: Phase 1 (1 to 5 years); Phase 2 (5 to 10 years); and Phase 3 (10 to 15 years).

TABLE 6-2. Implementation

| CLR Treatment Recommendation / FMSS Work Order | CLR Task Component/ FMSS Task Component | Phase / Priority Phase 1 (1 to 5 years) Phase 2 (5 to 10 years) Phase 3 (10 to 15 years) |
|---|---|---|
| Mound City Group | | |
| Task 1. Protect Views | Task 1.1 Establish screen/vegetation buffer at property edges Task 1.2 Thin veg to reveal mountain views Task 1.3 Screen Visitor Center | Phase 1 |
| Task 2. Relocate Visitor Center, Administrative, and Maintenance Buildings | Task 2.1 Determine new location for Administrative and Visitor Center Task 2.2 Remove Visitor Center, picnic shelter, Administrative, Maintenance Buildings, and relocate | Phase 3 |
| Task 3. Remove vehicular circulation | Task 3.1 Determine new access routes Task 3.2 Remove existing roads, parking areas | Phase 3 |
| Task 4. Investigate Small Scale Features | Task 4.1. Document features for significance Task 4.2 Repair/ remove as determined | Phase 2 |
| Task 5. Add Trails | Task 5.1 Create river access point Task 5.2 Create new trail through North 40 Task 5.3 Extend river trail Task 5.4 Create trail and connection across river to Hopeton Earthworks Task 5.5 Extend bike path from Tri County Triangle Trail to Mound City Group | Phase 2 |
| Task 6. Protect Soundscape | Task 6.1 Create agreement/partnership to mitigate noise | Phase 1 |
| Task 7. Establish Native Vegetation (North Forty) | Task 7.1 Transition North Forty from haying to native grasses and forbs | Phase 1 to 3 |
| Task 8. Maintain Previously Reconstructed Mounds (Mounds 1 through 23) | Task 8.1 Establish grass mix, mown 3-6" Task 8.2 Establish cobble marking on largest mounds (#1,2,3,4,5,7,8,18) | Phase 1 Phase 2 |

| CLR Treatment Recommendation / FMSS Work Order | CLR Task Component/ FMSS Task Component | Phase / Priority Phase 1 (1 to 5 years) Phase 2 (5 to 10 years) Phase 3 (10 to 15 years) |
|---|---|---|
| Mound City Group, Cont. | | |
| Task 9. Rehabilitate Mounds X1 & X2; 24 & 25 | Task 9.1 Conduct archeological investigations to verify Task 9.2 Rehabilitate mounds | Phase 3 |
| Task 10. Maintain Enclosure (interior space) | Task 10. Establish grass mix, mown 3-6" | Phase 1 |
| Task 11. Maintain Enclosure Walls | Task 11. Establish grass mix, mown 6-12" | Phase 1 |
| Task 12. Maintain Borrow pits | Task 12. Establish grass mix, mown 6-12" | Phase 1 |
| Task 13. Maintain Non-reconstructed borrow pit | Task 13. Establish grass mix, mown 6-12" | Phase 1 |
| CLR Treatment Recommendation / FMSS Work Order | CLR Task Component/ FMSS Task Component | Phase / Priority Phase 1 (1 to 5 years) Phase 2 (5 to 10 years) Phase 3 (10 to 15 years) |
| Hopeton Earthworks | | |
| Task 1. Protect Views and Land Use | Task 1.1 Establish vegetation to screen property edges | Phase 1 |
| Task 2. Visitor Parking, access | Task 2.1 Create visitor parking, visitor orientation | Phase 3 |
| Task 3. Remove gravel road | Task 3.1 Remove existing road | Phase 2 |
| Task 4. Add Trails | Task 4.1. Add a nature trail through the park unit, and connect trail to Mound City Group | Phase 3 |
| Task 5. Establish Native Vegetation (outside of earthworks) | Task 5.1 Transition vegetation from haying to native grasses and forbs | Phase 1 |
| Task 6. Maintain and Rehabilitate Great Circle, Square | Task 6.1 Verify extents and establish grass mix, mown 6-12" | Phase 2 |
| Task 7. Maintain earthwork enclosures (interior spaces) | Task 7.1 Transition from haying to establish grass mix, mown 3-6" | Phase 2 |
| Task 8. Maintain and Rehabilitate Parallel Walls, Circle A, B, and C | Task 8.1 Verify extents and establish grass mix, mown 6-12" | Phase 2 |
| Task 9. Maintain and Rehabilitate Mounds | Task 9.1 Verify extents and establish grass mix, mown 6-12" | Phase 3 |
| Task 10. Maintain Borrow pits | Task 10.1 Establish grass mix, mown 6-12" | Phase 2 |

| CLR Treatment Recommendation / FMSS Work Order | CLR Task Component/ FMSS Task Component | Phase / Priority Phase 1 (1 to 5 years) Phase 2 (5 to 10 years) Phase 3 (10 to 15 years) |
|--|--|---|
| Hopewell Mound Group | | |
| Task 1. Protect Views | Task 1.1 Establish vegetation to screen the adjacent land uses | Phase 1 |
| | Task 1.2 Remove utilities that cross earthworks | Phase 3 |
| Task 2. Visitor access | Task 2.1 Provide visitor parking area | Phase 2 |
| Task 3. Remove Sulphur Lick Road | Task 3.1 Work with agencies, community to provide a new route | Phase 3 |
| Task 4. Trails and river access | Task 4.1. Relocate Tri-County Trail away from earthworks | Phase 2 |
| | Task 4.2 Maintain nature trail and add overlook | |
| | Task 4.3 Provide creek access | |
| Task 5. Establish Native Vegetation (outside of earthworks) | Task 5.1 Transition vegetation from haying to native grasses and forbs | Phase 1 |
| Task 6. Maintain and Rehabilitate Great Enclosure, Square Enclosure, and D-shaped Enclosure | Task 6.1 Establish grass mix, mown 6-12" | Phase 1 |
| | Task 6.2 Verify extents and rehabilitate | Phase 3 |
| Task 7. Maintain earthwork enclosures (interior spaces) | Task 8.1 Transition from haying to establish grass mix, mown 3-6" | Phase 1 |
| Task 8. Maintain and Rehabilitate Mounds (5 verified) | Task 8.1 Establish grass mix, mown 6-12" | Phase 1 |
| | Task 8.2 Verify extents and rehabilitate | Phase 3 |
| Task 9. Verify and Rehabilitate Mounds (33 unverified) | Task 9.1 Verify Mounds, archeological research | Phase 1 |
| | Task 9.2 Establish grass mix, mown 6-12" | Phase 2 |
| | Task 9.3 Rehabilitate | Phase 3 |
| Task 10. Rehabilitate Ditches | Task 10.1 Establish grass mix, mown 3-6" | Phase 1 Phase 3 |
| Task 11. Maintain Borrow pits | Task 11.1 Establish grass mix, mown 6-12" | Phase 1 |

| CLR Treatment Recommendation / FMSS Work Order | CLR Task Component/ FMSS Task Component | Phase / Priority Phase 1 (1 to 5 years) Phase 2 (5 to 10 years) Phase 3 (10 to 15 years) |
|---|---|---|
| Seip Earthworks | | |
| Task 1. Protect Views and Land Use | Task 1.1 Establish vegetation to screen the school from the earthworks | Phase 1 |
| Task 2. Relocate Visitor Parking, picnic, access | Task 2.1 Determine new location for parking, visitor orientation Task 2.2 Remove picnic shelter, parking, and associated features. | Phase 3 |
| Task 3. Move Dill Road | Task 3.1 Determine new route, to be located off of earthwork features. Task 3.2 Remove existing road and utility poles | Phase 3 |
| Task 4. Add Trails | Task 4.1. Add a nature trail to follow Paint Creek and create a loop through the park unit Task 4.2 Connect trail to the greater greenway trail system | Phase 1 |
| Task 5. Document and remove Blackstone House and Fish Camp Buildings | Task 5.1 Document the Fish Camp buildings and related structures, and remove Task 5.2 Document the Blackstone House Task 5.3 Remove the Blackstone House, outbuildings, and other associated features (road, utilities) | Phase 1 - 2 |
| Task 6. Establish Native Vegetation (outside of earthworks) | Task 6.1 Transition vegetation from haying to native grasses and forbs | Phase 1 |
| Task 7. Maintain and Rehabilitate Large Circle | Task 8.1 Establish grass mix, mown 6-12" Task 8.2 Verify extents and rehabilitate circle | Phase 2 |
| Task 8. Maintain earthwork enclosures (interior spaces) | Task 8.1 Transition from haying to establish grass mix, mown 3-6" | Phase 1 |
| Task 9. Maintain Seip-Pricer Mound | Task 09.1 Establish cobble marking on mound | Phase 3 |
| Task 10. Maintain Conjoined Mound | Task 10.1 Verify extents, add soil to define mound, as determined necessary Task 10.2 Establish cobble marking on mound | Phase 3 |
| Task 11. Rehabilitate Small Circle and Large Square | Task 11.1 Establish grass mix, mown 6-12" Task 11.2 Verify extents and rehabilitate | Phase 1 Phase 3 |
| Task 12. Maintain Borrow pits | Task 12.1 Verify extents and establish grass mix, mown 6-12" | Phase 2 |

| CLR Treatment Recommendation / FMSS Work Order | CLR Task Component/ FMSS Task Component | Phase / Priority Phase 1 (1 to 5 years) Phase 2 (5 to 10 years) Phase 3 (10 to 15 years) |
|--|--|---|
| High Bank Works | | |
| Task 1. Protect Views and Land Use | Task 1.1 Establish a view to the river from the earthwork complex Task 1.2 Establish vegetation to screen the adjacent railroad tracks from the earthwork complex | Phase 1 |
| Task 2. Provide Visitor access | Task 2.1 Provide a new parking area and visitor access to the South Earthwork Task 2.2 Provide visitor parking area and safe passage across the railroad tracks | Phase 2 |
| Task 3. Remove gravel road | Task 3.1 Remove gravel roads and utilities that cross the earthworks | Phase 3 |
| Task 4. Add Trails and river access | Task 4.1. Add a nature trail to the river edge, with river access. Create a looped trail through the park unit. | Phase 2 |
| Task 5. Establish Native Vegetation (outside of earthworks) | Task 5.1 Transition vegetation from haying to native grasses and forbs | Phase 1 |
| Task 6. Maintain and Rehabilitate Great Circle | Task 6.1 Verify extents and establish grass mix, mown 6-12" | Phase 1 |
| Task 7. Maintain earthwork enclosures (interior spaces) | Task 8.1 Transition from haying to establish grass mix, mown 6-9" | Phase 1 |
| Task 8. Maintain and Rehabilitate Octagon | Task 8.1 Establish grass mix, mown 6-12" | Phase 1 |
| Task 9. Maintain and Rehabilitate Parallel Walls | Task 9.1 Verify extents and establish grass mix, mown 6-12" | Phase 2 |
| Task 10. Rehabilitate South Earthwork | Task 10.1 Verify extents and establish grass mix, mown 6-12" | Phase 2 |
| Task 11. Maintain Borrow pits | Task 11.1 Verify extents and establish grass mix, mown 6-12" | Phase 1 |

Page left intentionally blank.