

Attachment 2 - Listing of Burned Building Sites to be Cleaned Up:

September 18, 2018

Map Location #	DESCRIPTION	Square footage	Approx. date of Const	Building Use	Park Area	Foundation Type	Estimated Tons of Scrap Metal	Number of Ash Tests per Bldg Site	Estimated Tons of Ash	Estimated Tons of Conc & Masonry	Number of Soil Tests per Bldg Site	Septic Tank to be Demo'ed	Estimated CY Mulch per site @ 2" depth	Other notes
23067	BLDG# 616 Brandy Creek Sewer Plant Building	620	1970	WWTP Office	Brandy Cr	Conc. Slab	0.50	2	2.65	34.00	2	None	5	Conc Slab, Metal Electrical control panel + metal furniture. Protect existing water backflow preventer
23051	BLDG# 607 Housing (Artist Cabin)	1120	1968	Residence	Brandy Creek	Conc Footer & Basement Slab	0.25	2	4.75	96.00	2	Yes	9	Conc slab + CMU basement walls
22971	BLDG # 701 Cabin 1	400	1951	Sleeping Cabin	NEED Camp	post & pier	0.50	2	0.10	0.25	2	None	4	metal roofing, bunk beds + pier blocks
22972	BLDG # 702 Cabin 2	400	1951	Sleeping Cabin	NEED Camp	post & pier	0.50	2	0.10	0.25	2	None	4	metal roofing, bunk beds + pier blocks
22973	BLDG # 703 Cabin 3	400	1951	Sleeping Cabin	NEED Camp	post & pier	0.50	2	0.10	0.25	2	None	4	metal roofing, bunk beds + pier blocks
22975	BLDG# 705 Cabin 5	400	1951	Sleeping Cabin	NEED Camp	post & pier	0.50	2	0.10	0.25	2	None	4	metal roofing, bunk beds + pier blocks
22976	BLDG# 706 Cabin 6	400	1951	Sleeping Cabin	NEED Camp	post & pier	0.50	2	0.10	0.25	2	None	4	metal roofing, bunk beds + pier blocks
22977	BLDG # 707 Cabin 7	400	1951	Sleeping Cabin	NEED Camp	post & pier	0.50	2	0.10	0.25	2	None	4	metal roofing, bunk beds + pier blocks
22992	BLDG# 714 Cabin 14	400	1951	Sleeping Cabin	NEED Camp	post & pier	0.50	2	0.10	0.25	2	None	4	metal roofing, bunk beds + pier blocks
22994	BLDG# 715 Cabin 15	400	1951	Sleeping Cabin	NEED Camp	post & pier	0.50	2	0.10	0.25	2	None	4	metal roofing, bunk beds + pier blocks
22997	BLDG# 716 Cabin 16	400	1951	Sleeping Cabin	NEED Camp	post & pier	0.50	2	0.10	0.25	2	None	4	metal roofing, bunk beds + pier blocks
23001	BLDG # 720 Care Takers Shed	128	2011	Small Equipment storage	NEED Camp	Conc. Slab	1.50	2	3.65	4.00	2	None	4	Includes metal garage door, roofing, UTV, riding mower, log splitter, 180 LF Cyclone fence & conc slab
23093	BLDG# 200 RX Crew Office	1592	1965	Office	Whiskey Cr	Conc Footer	0.75	3	4.00	75.00	3	Yes	12	dirt crawl space, wood stove & 280 LF Cyclone Fence
109223	BLDG# 209 Garage at Bldg# 200	500	1969	Storage	Whiskey Cr	Conc. Slab	0.25	2	0.45	25.00	2	No	5	Conc slab, sidewalks + conc slope paving
229955	Whiskey Creek Store/ Post Office	2950	?	Vacant	Whiskey Cr	Conc. Slab	3.00	7	12.70	87.00	7	Yes	22	Includes conc slabs, approx. 10 CY stucco (dispose with Ash), Remove pressure tank @ well site, Do not remove asphalt parking area pavement
229843	BLDG# 206 Aurtorie/Whiskey Creek Ranger Offices	1600	1969	Office	Whiskey Cr	Conc Footer	3.50	4	4.45	178.00	4	No	15	Dirt crawl space, includes exercise equipment, adjacent garage slab, CMU planter walls, & walks. Do not remove perimeter retaining walls, septic tank, cap water & sewer lines. Do not disturb adjacent Private home site.
23178	BLDG# 402 Park Housing Unit	2479	1962	Residence	Carr Powerhouse	Slab	1.00	6	6.95	200.00	6	Yes	19	septic tank not yet found, regrade slope at end of driveway where timber wall burned, remove stone walls and place rubble in bldg excavation to refill hillside cut
23169	BLDG# 400 Park Housing Unit	832	1962	Residence	Carr Powerhouse	Conc Footer & post /Pier	4.25	2	4.65	52.00	2	Yes	12	Includes removal of Carport #401, also remove 7 CY stone patio+ walls & place in Bldg 402 excavation
23280	BLDG #509 Eldorado Stamp Mill	240	1940	historic exhibit	Tower House Historical District	Timber	0.25	2	0.25	0.00	2	None	0	Only remove metal roofing & burned timbers, non-hazardous ash, no soil excavation
23283	BLDG # 510 Eldorado Mine Equipment Shed	1260	1945	historic exhibit	Tower House Historical District	Stone	0.50	3	0.13	0.00	3	None	0	Only remove metal roofing & burned timbers, non-hazardous ash, no soil excavation
23292	BLDG # 515 Housing	1768	1965	Residence	French Gulch	Conc Footer	0.50	4	5.00	106.00	4	Yes	15	garage & basement slabs, Remove chimney & 8,000 gallon steel water tank, do not remove new metal roofing
35516	McDermott House Storage Shed	160	1956	Vacant	Grizzly Gulch	Slab	0.25	2	0.25	4.00	2	None	2	Remove metal mining equipment
35518	McDermott Site Stamp Mill	100	1950	Non Operational	Grizzly Gulch	Slab	10.25	2	0.00	1.00	2	No	2	remove top from 8'x8' conc. water tank, fill with soil, also remove mining equipment from surrounding area
35517	McDermott Site Welding Shop	1105	1956	Vacant	Grizzly Gulch	Slab	7.00	3	2.75	17.00	3	None	0	retain shop floor slab, remove roofing, equipment + metal tanks, and concrete water tank at well site above shop
35515	McDermott House	1872	1956	Vacant	Grizzly Gulch	Conc Footer & post /Pier	0.50	5	2.65	106.00	5	No	15	dirt crawl space, burned fiberglass roof panels
249320	BLDG# 900 CDF Office	2418	1958	Vacant	Crystal Cr	Conc Footer & post /Pier	5.00	6	6.85	118.00	6	No	19	Metal Roof & Transite siding
249326	BLDG# 911 Mess Hall	3312	1958	Vacant	Crystal Cr	Slab	10.00	8	9.00	133.00	8	No	25	Metal Roof, 18x18x8 CMU interior room, Transite siding, Commercial kitchen fixtures
249330	BLDG# 913 Barracks	9009	1958	Vacant	Crystal Cr	Slab	15.00	22	25.50	370.00	22	No	66	Metal Roof, transite siding & Boiler
Total Square footage		34,925			Estimated Totals =		68.75	105	97.53	1,608.25	105	6	283	